CIVIL SITE PLANS: CIRCLE K - NTI AIRPORT BLVD WILMINGTON - NC.115 WILMINGTON, NORTH CAROLINA 28405

ARCHITECT:

TBD

OWNER:

NEW HANOVER COUNTY 230 GOVERNMENT CENTER DR WILMINGTON, NC 28403

	SITE PLAN SUMMARY
PROJECT:	CIRCLE K - NTI - AIRPORT BLVD WILMINGTON - NC.115
OWNER:	NEW HANOVER COUNTY
PROJECT ADDRESS:	0 AIRPORT BLVD, WILMINGTON, NC 28405
PID:	R04200-001-025-F00
JURISDICTION:	NEW HANOVER COUNTY
ZONING:	AC (AIRPORT COMMERCE)
EXISTING USE:	VACANT
PROPOSED USE:	CONVENIENCE STORE W/ GAS SALES
FLOOD ZONE:	NOT LOCATED IN FLOOD HAZARDS AREA PER FEMA MAP #3720312900K (EFFECTIVE 08/28/2018)
PROPOSED TRACT AREA:	2.13 AC (92,834.78 SF)
DISTURBED AREA:	10.00 AC (435,600 SF)
EXISTING IMPERVIOUS SURFACE AREA:	91.5 SF (0.10%)
PROPOSED IMPERVIOUS SURFACE AREA:	69,896 SF
PROPOSED % IMPERVIOUS	75%
TYPE OF BUILDING CONSTRUCTION:	CONVENIENCE STORE: V-B (NON-SPRINKLERED)
TYPE OF CANOPY CONSTRUCTION:	II-B
PROPOSED CONVENIENCE BUILDING SQUARE FOOTAGE:	5,200 SF
VEHICLE PARKING SUMMARY: REQUIRED	CONVENIENCE STORES W/ GAS SALES: 1 SPACE PER 400 SQUARE FEET OF GFA 5,200 SF / 400 SF = 13 SPACES REQUIRED; TOTAL = 13 SPACES (1 MUST BE ADA SPACES)
VEHICLE PARKING SUMMARY: PROVIDED	23 PARKING SPACES 2 ADA SPACES (1 IS VAN ACCESSIBLE) TOTAL: 25 SPACES

NEW HANOVER COUNTY

DEVELOPER:

CIRCLE K STORES INC ANDY PRIOLO 1100 SITUS COURT, SUITE #100 RALEIGH, NC 27606 PH: (919) 566-1714 FAX: (919) 777-5139


CIVIL ENGINEER:

TIMMONS GROUP 5410 TRINITY ROAD **SUITE 102** RALEIGH, NC 27607

PROJECT MANAGER BRIAN DOWNS BRIAN.DOWNS@TIMMONS.COM PH: (919) 866-4504

ENGINEER OF RECORD RICK BAKER, PE RICK.BAKER@TIMMONS.COM PH: (919) 866-4939

Sheet Number	Sheet Title
C0.0	COVER SHEET
C1.0	EXISTING CONDITIONS PLAN
C1.1	EXISTING CONDITIONS PLAN
C1.2	DEMOLITION PLAN
C1.3	DEMOLITION PLAN
C2.0	SITE LAYOUT PLAN
C2.1	PAVING PLAN
C2.2	VEHICULAR ROUTING PLAN
C3.0	GRADING AND DRAINAGE PLAN
C3.1	GRADING AND DRAINAGE PLAN
C3.2	SPOT GRADING PLAN
C3.3	PRIVATE STREET 1 - PLAN AND PROFILE
C3.4	PRIVATE STREET 2 - PLAN AND PROFILE
C3.5	PHASE IIIA DRY POND - PLAN AND PROFILE
C3.6	PHASE IIIA DRY POND - DETAILS
C3.7	PHASE IIIB DRY POND - PLAN AND PROFILE
C3.8	PHASE IIIB DRY POND - DETAILS
C3.9	SCM DETAILS
C4.0	EROSION CONTROL PLAN - PHASE I
C4.1	EROSION CONTROL PLAN - PHASE I



GENERAL NOTES:

- 1. IT SHALL BE UNLAWFUL FOR ANY PERSON TO MAKE ANY EXCAVATION OR DO ANY OTHER WORK WHICH MAY CAUSE A DANGEROUS CONDITION IN OR ON ANY STREET, ALLEY, SIDEWALK, PUBLIC WAY OR PUBLIC PLACE IN THE CITY, UNLESS A WRITTEN PERMIT IS FIRST OBTAINED FROM AN OFFICER OF THE CITY VESTED WITH AUTHORITY TO GRANT THE SAME. NO PERMIT SHALL BE ISSUED IN ANY CASE WHERE A BOND IS REQUIRED UNTIL A BOND SHALL HAVE BEEN EXECUTED.
- 2. ALL CONTRACTORS SHALL VISIT THE PROJECT TO FAMILIARIZE THEMSELVES WITH SITE CONDITIONS PRIOR TO BIDDING OR CONSTRUCTION. BY SUBMITTING A BID, THE CONTRACTOR AND HIS SUBCONTRACTORS ARE CONFIRMING THAT THEY HAVE VISITED THE SITE AND HAVE INCLUDED IN THEIR BID ANY ADDITIONAL ITEMS OF CONSTRUCTION THAT MAY BE REQUIRED DUE TO EXISTING SITE CONDITIONS.
- 3. CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).

NTS

PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS





SURVEYOR:

PARAMOUNTE ENGINEERING, INC TIM CLINKSCALES, P.E., PLS 122 CINEMA DRIVE WILMINGTON, NC 28403 PH: (910) 791-6707 TCLINKSCALES@PARAMOUNTE-ENG.COM

C4.2	EROSION CONTROL PLAN - PHASE II
C4.3	EROSION CONTROL PLAN - PHASE II
C4.4	NPDES PLAN
C4.5	NPDES PLAN
C4.6	NPDES NOTES AND DETAILS
C5.0	UTILITY PLAN
C5.1	UTILITY PLAN
C5.2	SANITARY SEWER PLAN AND PROFILE
C5.3	WATER MAIN PLAN AND PROFILE
C6.0	LANDSCAPE PLAN
C6.1	LANDSCAPE PLAN
C7.0	NOTES AND DETAILS
C7.1	NOTES AND DETAILS
C7.2	NOTES AND DETAILS
C7.3	NOTES AND DETAILS
C7.4	NOTES AND DETAILS
C7.5	NOTES AND DETAILS
C7.6	NOTES AND DETAILS
C7.7	NOTES AND DETAILS
L1.0	SITE LIGHTING PLAN
L1.1	SITE LIGHTING DETAILS









ese plans and associated documents are the exclusive property of LIMMONS GROUP and may not be reproduced in whole or in part and shall not be used wited to construction, bidding, and/or construction staking without the express written consent of TIMMONS GROUP


nstruction, bidding, and/or construction staking without the express written






SCALE 1"=40'

40'



NCDOT PLANS



<u>)/11</u> <u>)/2</u>1

DATE

09/02/2020

DRAWN BY

A. MAY

DESIGNED BY

B. DOWNS

CHECKED BY

R. BAKER

SCALE

AS SHOWN

S

Ζ

Ζ

Ο


M

JOB NO.

7630.054

SHEET NO.


C1.3



- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH NEW HANOVER COUNTY AND NCDOT STANDARDS AND SPECIFICATIONS.
- 2. ALL DIMENSIONS ARE TO FACE OF CURB, EDGE OF PAVING, BUILDING WALL FACE OR PROPERTY LINE UNLESS OTHERWISE NOTED. 3. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, UTILITIES AND GRADES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE ENGINEER OF
- ANY EXISTING DISCREPANCIES PRIOR TO COMMENCING ANY RELATED CONSTRUCTION. 4. AT LEAST 72 HOURS PRIOR TO CONSTRUCTION OR EXCAVATION THE
- CONTRACTOR SHALL NOTIFY "NORTH CAROLINA ONE CALL" (811) OR (1-800-632-4949) TO HAVE EXISTING UTILITIES LOCATED.
- PARKING SPACES ARE 9.5' WIDE X 18' LONG MINIMUM EXCEPT HANDICAP SPACES WHICH ARE 8.0' WIDE MINIMUM WITH 8.0' VAN ACCESS AND 5.0' STANDARD ACCESS AISLES.
- REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS OF THE BUILDING. CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DIMENSIONAL CONFLICTS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- 8. ALL CURB AND GUTTER ONSITE SHALL BE 24" WIDE. 9. ALL DISTURBED CURB & GUTTER AND ASPHALT SHALL BE REPLACED PER NEW
- HANOVER COUNTY OR NCDOT STANDARDS AND SPECIFICATIONS. 10. ALL DRIVEWAY DESIGN AND CONSTRUCTION MUST COMPLY WITH NEW HANOVER COUNTY SPECIFICATIONS. DRIVEWAYS SHALL BE PERMITTED
- SEPARATELY. 11. NO SIGHT OBSTRUCTING OR PARTIALLY OBSTRUCTING WALL, FENCE, FOLIAGE, BERMING, PARKED VEHICLES OR SIGN BETWEEN THE HEIGHTS OF TWENTY-FOUR (24) INCHES AND EIGHT (8) FEET ABOVE THE CURB LINE ELEVATION, OR THE NEAREST TRAVELED WAY IF NO CURBING EXISTS, SHALL BE PLACED WITHIN A SIGHT TRIANGLE OF A PUBLIC STREET, PRIVATE STREET OR DRIVEWAY CONTAINED EITHER ON THE PROPERTY OR ON AN ADJOINING PROPERTY.

|--|

	SITE LAYOUT KEYNOTES
NUMBER	DESCRIPTION
CS01	C-STORE BUILDING, REFER TO ARCHITECTURAL AND MEP PLANS BY OTHERS.
CS02	DUMPSTER ENCLOSURE AND BOLLARDS; REFER TO
CS05	ARCHITECTURAL PLANS BY OTHERS. GAS CANOPY; REFER TO CANOPY PLANS BY OTHERS.
CS07	UST TANKS AND PAD; REFER TO FUELING PLANS BY OTHERS
	FOR PAD SIZING AND PAVING DESIGN.
CS10	PYLON SIGN; FURNISHED AND INSTALLED BY OTHERS. VERIFY EXACT LOCATION AND DESIGN BEFORE ROUGH-IN. PERMITTED BY OTHERS.
CS11	AIR AND WATER MACHINE; PROVIDE 3'x6' CONCRETE PAD. REFER TO DETAIL CK-160.
CS12	AIR AND WATER MACHINE PAVEMENT MARKING; REFER TO DETAIL CK-165.
CS13	TRANSFORMER PAD; GC TO COORDINATE LOCATION WITH LOCAL PROVIDER. LOCAL PROVIDER CAN SUPERSEDE THE PROPOSED TRANSFORMER PAD LOCATION.
CS14	ROOF LADDER PAD; 4'X6' STANDARD DUTY CONCRETE IF LOCATED IN LANDSCAPE AREA.
CS16	CO2 TANK AND STORAGE CABINET; 4'x4' STANDARD DUTY CONCRETE PAD IF LOCATED IN LANDSCAPE AREA.
CS17	BUILDING SERVICE ENTRANCE SECTION; 3.5'x7' STANDARD DUTY
	CONCRETE PAD IF LOCATED IN LANDSCAPE AREA.
CS18	OUTDOOR SEATING; REFER TO PLAN FOR DIMENSIONS. THREE SEAT ROUND OUTDOOR SEATING TABLE; REFER TO
CS20	DETAIL CK-195 (TYP.). REFER TO PLAN FOR COUNT.
CS21	CUSTOMER ONLY SEATING SIGN; REFER TO DETAIL CK-199.
CS23	BICYCLE RACK; REFER TO DETAIL CK-198 OR LOCAL REQUIREMENT.
	4" BOLLARD AND COVER, REFER TO DETAIL CK-180 AND CK-197
CS24	(TYP.). CENTER ON ADA STRIPING. 5' ON CENTER SPACING. REFER TO PLAN FOR COUNT.
0005	4" BOLLARD AND COVER, REFER TO DETAIL CK-180 AND FUELING
CS25	PLANS FOR LOCATION AND COUNT (TYP.).
CS27	ACCESSIBLE PARKING SIGN (TYPICAL - PER ADA AND LOCAL CODES) R7-8A (MUTCD) MOUNTED IN A BOLLARD; REFER TO DETAIL CK-185.
CS28	VAN ACCESSIBLE PARKING SIGN (TYPICAL - PER ADA AND LOCAL REQUIREMENTS) R7-8A (MUTCD) MOUNTED IN A BOLLARD; REFER TO DETAIL CK-185.
CS29	ADA ACCESSIBLE PARKING SPACE, AISLE, AND SYMBOL STRIPING; REFER TO DETAIL CK-105 AND CK-110. PER ADA AND LOCAL CODES.
CS32	24" CURB & GUTTER; REFER TO DETAIL CK-120 AND CK-125.
CS33	30" WIDE CONCRETE COLOR BAND FLUSH CURB; REFER TO DETAIL CK-197.
CS34	LIGHT POLE BASE (TYPICAL - PER LIGHTING PLAN); REFER TO DETAIL CK-190 AND ARCHITECTURAL PLANS BY OTHERS.
CS36	DIRECTIONAL TRAFFIC ARROW (PER LOCAL CODES); REFER TO DETAIL CK-115 (TYP.).
CS38	EXISTING SIGNALIZED INTERSECTION
CS56	DOG WASTE STATION; TO BE PROVIDED BY AND INSTALLED BY CIRCLE K.
CS58	MPD; REFER TO DETAIL CK-200 (TYP.).
S01	RIGHT-OF-WAY (TYP.)
S02	LEASE BOUNDARY (TYP.)
S28 S34	EXISTING ROAD CENTERLINE RIGHT IN / RIGHT OUT DRIVEWAY
S34 S35	ROAD WIDENING FOR RIGHT TURN LANE
S41	PARKING STALL STRIPING PER LOCAL CODES (TYP.)
S44	10' X 70' SIGHT DISTANCE TRIANGLE (TYP.)
S53	"RIGHT TURN ONLY" SIGN; R3-5 (MUTCD)
S60	PROPOSED CENTERLINE; TO BE DESIGNED BY OTHERS
S61	
S62	1' 6" NCDOT MOUNTABLE CURB 4' WIDE, 5" HIGH CONCRETE MONOLITHIC ISLAND PER NCDOT
S63	STD 852.01
S64	MUTCD R4-7 MEDIAN SIGN
S65	TRAFFIC SIGNAL MODIFICATIONS. REFER TO TRAFFIC SIGNAL PLANS.
S66	30' WIDE CFPUA SANITARY SEWER EASEMENT
S67	20' WIDE CFPUA WATER EASEMENT
S68	CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).
S69	CIRCLE K FUNDED CONSTRUCTION WORK
S70	ILM FUNDED CONSTRUCTION WORK
S71	30"x30" R1-1 "STOP" SIGN AND 24" WIDE "STOP" BAR
S72	VARIABLE WIDTH SCM ACCESS EASEMENT



 \mathbf{Y}

 \bigcirc

2

Н \bigcirc


JOB NO.


37630.054


SHEET NO.

C2.0

I	Linear Length Adjustment
	1
	1
	0.25
	1
	2
	1
	1
	1
	1
	1











PAVING INSET - SCALE 1" = 30'


PAVING KEYNOTES							
NUMBER	HATCH	DESCRIPTION					
P01		EXISTING PAVEMENT TO REMAIN UNDISTURBED.					
P04	AAA	HEAVY DUTY ASPHALT PAVING; REFER TO PAVEMENT SECTIONS DETAIL.					
P05		DOT ASPHALT; REFER TO PAVEMENT SECTIONS DETAIL.					
P08		STANDARD DUTY CONCRETE PAVING; REFER TO PAVEMENT SECTIONS DETAIL.					
P09		HEAVY DUTY CONCRETE PAVING; REFER TO PAVEMENT SECTIONS DETAIL.					
P13		CONCRETE SIDEWALK; REFER TO PAVEMENT SECTIONS DETAIL.					
P14		4" GRAVEL					
P16		BUILDING PAD; REFER TO ARCHITECTURAL PLANS BY OTHERS.					
P18		TRANSFORMER PAD PER UTILITY PROVIDER SPECIFICATIONS.					
P19		CONCRETE ISLAND PER NCDOT DETAIL 852.01, 852.02, AND 852.10.					
P20		CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).					
P21		CIRCLE K FUNDED CONSTRUCTION WORK					
P22		ILM FUNDED CONSTRUCTION WORK					
CP20	$\begin{array}{c} \bullet \bullet$	CONCRETE PAVING OVER UST TANKS. REFER TO FUELING PLANS BY OTHERS FOR DETAILS.					
CP21		THICKENED EDGE; REFER TO DETAIL CK-135 AND CK-150.					
CP22		REFER TO CONCRETE PAVEMENT JOINT DETAIL (TYP.); REFER TO DETAIL CK-175.					
CP23		SPECIALTY CONCRETE; REFER TO KEYNOTES ON SITE					
NOTE: CURE		T HATCHED. REFER TO SITE LAYOUT PLAN FOR ADDITIONAL					















	~~~					GF	RADING	AND STORM DRAINAGE NOTES			
STRUCTURE #			TABLE SCRIPTIO	N		1.	CONTR	ACTOR SHALL CALL "NORTH CAROLINA ONE CALL" (811) AT LEAST 3-12	WHITH CA	R0////	
EW100	N/A	NCDOT 838.80			L	2.	REPOR	ESS DAYS PRIOR TO DIGGING TO HAVE EXISTING UTILITIES LOCATED. T ANY DISCREPANCIES TO THE ENGINEER. ACTOR TO COORDINATE ACTIVITIES WITH UTILITY COMPANIES	THE SS	TONT	
EW101	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L	2.	INVOL\	/ED IN ANY RELATED RELOCATION (I.E. POWER POLES, TELEPHONE TALS, WATER METERS, ETC.).	SEA 1225	50	WH11/
EW102	N/A	NCDOT 838.80				3.	EXISTI	NG UTILITIES SHOWN ARE BASED ON FIELD SURVEYS AND THE BEST BLE RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY	FECT WGIN	EBOOD NI	
EW103 EW104	N/A N/A	NCDOT 838.80 NCDOT 838.80					BETWE	TIONS PRIOR TO BEGINNING CONSTRUCTION. ANY DISCREPANCIES EN ACTUAL FIELD CONDITIONS AND THE PLANS SHALL BE REPORTED		04/21/20	20
EW104	N/A	NCDOT 838.80				4.	THE CA	E ENGINEER IMMEDIATELY. ATCH BASINS AND YARD INLETS SHALL BE CONSTRUCTED IN THE			
EW108	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L		CONTR	IONS SHOWN UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE ACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES IN ATCH BASIN ELEVATIONS OR THE PROPOSED PIPE SLOPES TO THE	Eog		
EW109	N/A	NCDOT 838.80					ENGIN	EER. THE CONTRACTOR IS ALSO RESPONSIBLE TO REPORT ANY ICTS BETWEEN ANY UTILITY, STORM DRAIN LINE, WATER LINE, SEWER	IE NC 27607 .timmons.		i
EW200	N/A	NCDOT 838.80						R ANY OTHER PROPOSED OR EXISTING STRUCTURE TO THE	, tim Lim		
EW203 EW204	N/A N/A	NCDOT 838.01 NCDOT 838.01				5.	COMM	DISTURBING PERMIT WILL BE REQUIRED PRIOR TO THE ENCEMENT OF ANY LAND-DISTURBING ACTIVITIES.	.ED AT T .ED AT T .CE .Raleigh, 24 wwv	N SUBM:	
EW205	N/A	NCDOT 838.01				6.	BOXES	ISTING VAULTS, MANHOLES, STORM DRAIN STRUCTURES, VALVE , CLEANOUTS, ETC. SHALL BE ADJUSTED AS NEEDED TO MATCH	EPAR <b>OFFI</b> 02   33.81	ESCRIPTION CFPUA REVIEV STORMWATER	
EW206	N/A	NCDOT 838.01	CONCRE	TE ENDWAL	L	7.	ALL BA	ED GRADE. CKFILL, COMPACTION, SOILS TESTING, ETC. SHALL BE PERFORMED BY WNER'S INDEPENDENT TESTING LABORATORY.	AAWING PR <b>RALEIGH</b> ad, Suite 1 FAX 919.80	CRIPTION PUA REVII DRMWATE	
EW207	N/A	NCDOT 838.80				8.	ALL SP	OT ELEVATIONS INDICATED ARE AT TOP OF CURB UNLESS NOTED WISE. ALL ELEVATIONS ARE BASED ON VERTICAL DATUM NAVD88.	DRAWI <b>RAL</b> toad, S FAX		'I I I
EW209 EW210	N/A	NCDOT 838.01 NCDOT 838.80				9.	A PRE-	CONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO ANY GRADING OR INSTALLATION OF EROSION CONTROL MEASURES.		REVISION VISION PE	
EW210	N/A N/A	NCDOT 838.00				10.	ALL HA	NDICAP PARKING SPACES AND STRIPED ACCESSIBILITY AISLES ARE /E NO MORE THAN A 1:50 (2.0%) SLOPE IN ALL DIRECTIONS. ALL	THIS 410 Trinity 19.866.495	REVI: VISIO ER CO	
EW300	N/A	NCDOT 838.80					LENGT	ALKS ARE TO HAVE NO MORE THAN A 1:20 (5.0%) SLOPE FOR THE H OF THE SIDEWALK AND NO MORE THAN A 1:50 (2.0%) SLOPE FOR	54 TEL 91	RENOVE	
EW400	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L	11.	CONTR	DTH OF THE SIDEWALK. ACTOR TO IDENTIFY ALL NECESSARY SPILL CURB SECTION		HANO	
FE214	N/A		D END SE				STRUC	IONS AND INSTALL TO ENSURE POSITIVE DRAINAGE TO STORM TURES. TRACTOR NOTICES ANY DISCREPANCIES IN ANY OF THESE SLOPE	OURS.		
FE215	N/A					12.	REQUI	TRACTOR NOTICES ANY DISCREPANCIES IN ANY OF THESE SLOPE REMENTS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT WNER PRIOR TO POURING ANY CONCRETE SO THAT A SOLUTION CAN	HROUGH (		
FE301 FE302	N/A N/A		D END SE			13.	BE FOL				
JB105		NCDOT 840.34 TRAFI					POINTS	BUT IT SHOULD NOT BE ASSUMED THAT ALL NECESSARY SPOT TIONS ARE SHOWN. DUE TO SPACE LIMITATIONS, THERE MAY BE	ACHIEVED	DATE /11/2020 /21/2020	
JB201	20.00	NCDOT 840.34 TRAFI	FIC BEAR	ING JUNCTI	ON BOX		OTHER CONSII	CRITICAL SPOTS NOT LABELED THAT SHOULD BE TAKEN INTO DERATION. THE CONTRACTOR SHALL REVIEW THE GRADING PLAN IN		DAT 09/11/ 09/21/	
JB208	23.20	NCDOT 840.34 TRAFI					AND FO	AND SHALL ENSURE THAT ALL CRITICAL GRADE POINTS ARE STAKED DLLOWED TO PROVIDE POSITIVE DRAINAGE.	NOISIN		2 <u>     </u> Ate
JB211	23.00 18.50	NCDOT 840.34 TRAFI				14.	UNDIS	NG VEGETATION WITHIN TREE PROTECTIVE AREAS SHALL REMAIN FURBED UNLESS NOTED OTHERWISE. ANY AND ALL LANDSCAPING KISTING TREES AND SHRUBS TO REMAIN WHICH ARE DAMAGED	YOUR V	09/02	2/2020
RS101A RS202B	18.50	RISER STRU RISER STRU					DURIN	G DEMOLITION OR CONSTRUCTION SHALL BE REPLACED BY THE ACTOR USING A LICENSED LANDSCAPE CONTRACTOR AT NO	×		WN BY MAY
YI106	22.08	NCDOT 840.14 (			ET	15.	ADDITI	ONAL COST TO THE OWNER. RADING CONTRACTOR SHALL COMPLY WITH ALL STATE CODES IN			
YI213	18.85	NCDOT 840.18 (	CONCRET	E DROP INL	ET		OBSER	VING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. THE NG CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES			OWNS
				_			INSPEC	EACH RAINFALL EVENT OR AS DIRECTED BY THE EROSION CONTROL CTOR OR THE ENGINEER.		CHEC	KED BY
	UPSTRE	STORM PIP				16.	DISPOS	RADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE SAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED			AKER
PIPE #	INVER		SLOPE		DESCRIPTION	17.	OFF-SI	G CONSTRUCTION AND FOR OBTAINING ALL APPLICABLE PERMITS FOR TE STOCKPILES AND/OR WASTE AREAS. TCH BASINS MUST BE MARKED "DUMP NO WASTE DRAINS TO			ale Hown
EW-EXPIPE2	14.00	13.97	0.47%	7.42 LF	24 inch RCP	17.	STREA	M" OR EQUIVALENT. ACTOR TO MOVE EXCESS SOIL EXCAVATED FROM STORMWATER	•		
EW-EXPIPE1 101A-101	19.96 14.35	19.92	0.48%	8.00 LF 46.59 LF	24 inch RCP 18 inch RCP		CONTR	COL MEASURES TO DESIGNED STOCKPILE AREA ON ILM PROPERTY. DINATE WITH ILM CONTACT ON EXACT LOCATION. REFER TO INSET.	•	15	
103-102	16.35	16.00	0.82%	42.86 LF	30 inch RCP						
105-104	16.93	16.50	1.00%	42.75 LF	30 inch RCP			GRADING PLAN KEYNOTES		NC	
106-105	18.25	17.31	1.00%	93.60 LF	24 inch RCP		NUMBER	DESCRIPTION			
107-106	21.75 22.71		3.00% 0.30%	89.24 LF 68.21 LF	15 inch RCP 18 inch Class IV RCP		CG01	TAPER CURB AND GUTTER TO FULL HEIGHT OVER 10' (TYP.); REFER TO DETAIL CK-135. DAYLIGHT ROOF DRAIN DOWN SPOUTS TO GRADE (TYP.). REFER		Z	
201-200	12.89	12.80	0.30%	30.00 LF	30 inch RCP		CG03	TO DETAIL CK-215. STORM CLEANOUT; REFER TO DETAIL CK-210. TRAFFIC RATED IF		0	
202-201	13.05	12.93	0.30%	39.27 LF	30 inch RCP		CG05	WITHIN PAVEMENT (TYP.). ROOF DRAIN SYSTEM, REFER TO PLAN FOR SIZE AND MATERIAL.		Ē	Ā
204-203	14.55	14.25	1.00%	30.00 LF	42 inch RCP		CG06 CG09	MINIMUM COVER OF 2' AND MINIMUM SLOPE OF 1.00%. DAYLIGHT CANOPY DRAINS OUTLET TO GRADE (TYP.)	52	NG	
206-205	14.55	14.25	1.00%	30.00 LF	42 inch RCP		G23	ADA STALLS (MAX SLOPE 1:50) SIDEWALK (ADA ACCESS ROUTE MAX CROSS SLOPE 1:50; MAX			
208-207	15.08 19.20		1.00% 0.54%	27.64 LF 55.37 LF	30 inch RCP 30 inch RCP		G24 G30	LONG. SLOPE 1:20) MATCH EXISTING PAVEMENT ELEVATION		Γ	<b>T</b> <b>P</b>
211-210	15.04	14.80	1.00%	23.73 LF	42 inch RCP		G31 G32	RIP RAP PAD OVER FILTER FABRIC (REFER TO SIZING CHART) RISER STRUCTURE		١٧	
212-211	18.70	18.20	0.87%	57.63 LF	36 inch RCP		G40	24" CONCRETE FLUME CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE			
213-211	15.60		0.50%	71.34 LF	30 inch RCP		G41	SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).			RACO
215-214	19.15		0.30%	47.43 LF	18 inch RCP		G42 G43	CIRCLE K FUNDED CONSTRUCTION WORK		BL	
302-301	23.52	23.20	0.35%	92.29 LF	18 inch Class IV RCP		G43 G44	VARIABLE WIDTH SCM ACCESS EASEMENT			S ANO
21			22	Y \						$\sim$	G AI
1		× *	/ /		2/2	/ / 		EW101 CLASS 'B'         •         EW202, 204, & 206 CLASS 'I'	ARG	Q	Z
	_	- ²⁰ / /	` `	\				12'L X 6'W X 18"D     40'L X 22'W X 24"D       ● EW102     ● FE214		RF	DIO
/	,	/\/-			' <u>+</u>			CLASS 'B'         CLASS 'A'           16'L X 6'W X 18"D         6'L X 4.5'W X 12"D	RTI	٩I	GRA
		SAN -	```	\ \				• <u>EW104</u> • <u>FE301</u> CLASS 'B' CLASS 'A'	Nov	<b>I</b>	U MILM
		, <b>*</b>		1				12'L X 6'W X 18"D       6'L X 4.5'W X 12"D         • <u>EW108</u> •         CLASS 'A'       CLASS 'A'		Z	>
20		/		1				CLASS 'A' CLASS 'A' 6'L X 4.5'W X 12"D 8'L X 6'W X 12"D • EW200		ے ۱	
		/				\ \	1	CLASS 'B' 18'L X 9'W X 18"D		$\mathbf{X}$	
			<.			١				Ш	
		SA									
			, 21	/			ſ			RC	
,	/						+			CI	
  19				\ \	`\ ``	_					3 NO.
	( a	FOR CONSTR	1		\		\D 83	SCALE 1"=40'			0.054
					Y, CAPE FEAR		Z			SHEE	ET NO.
	INT C	ΤΔΝΙΠΔΡΠς ςΓ						0 40' 80'		-	- <i>-</i>
Q, AND NC	DOTS	TANDARDS, SF		JATION	5, AND DETAILS			0 40' 80'		C3	3.1



			ORM STRUCTURE				GR		G AND STORM DRAINAGE NOTES		
	STRUCTURE #	1 1		SCRIPTIO	N		1.		RACTOR SHALL CALL "NORTH CAROLINA ONE CALL" (811) AT LEAST 3-12		ARO
STOCKPILE	EW100	N/A	NCDOT 838.80			 L		REPO	NESS DAYS PRIOR TO DIGGING TO HAVE EXISTING UTILITIES LOCATED. ORT ANY DISCREPANCIES TO THE ENGINEER.	IN OFFES	STONE
SITE	EW101	N/A	NCDOT 838.80				2.	INVOL	RACTOR TO COORDINATE ACTIVITIES WITH UTILITY COMPANIES LVED IN ANY RELATED RELOCATION (I.E. POWER POLES, TELEPHONE	SE SE	AL 530
	EW102	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L	3.	EXIST	STALS, WATER METERS, ETC.). FING UTILITIES SHOWN ARE BASED ON FIELD SURVEYS AND THE BEST	TE CONTROL	NEEROO
	EW103	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L		CONE	ABLE RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY DITIONS PRIOR TO BEGINNING CONSTRUCTION. ANY DISCREPANCIES		BAKKI
	EW104	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L		TO TH	VEEN ACTUAL FIELD CONDITIONS AND THE PLANS SHALL BE REPORTED HE ENGINEER IMMEDIATELY.		09/21/2020
	EW107	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L	4.		CATCH BASINS AND YARD INLETS SHALL BE CONSTRUCTED IN THE . TIONS SHOWN UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE		
	EW108	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L			RACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES IN CATCH BASIN ELEVATIONS OR THE PROPOSED PIPE SLOPES TO THE	com	
	EW109	N/A	NCDOT 838.80						NEER. THE CONTRACTOR IS ALSO RESPONSIBLE TO REPORT ANY FLICTS BETWEEN ANY UTILITY, STORM DRAIN LINE, WATER LINE, SEWER	27607 mons	
	EW200	N/A	NCDOT 838.80					LINE ( ENGIN	OR ANY OTHER PROPOSED OR EXISTING STRUCTURE TO THE NEER.	THE v.tim	l EW ER SUBMITT/
	EW203 EW204	N/A N/A	NCDOT 838.01 NCDOT 838.01				5.		ND DISTURBING PERMIT WILL BE REQUIRED PRIOR TO THE MENCEMENT OF ANY LAND-DISTURBING ACTIVITIES.	D AT aleigh 4 ww	V SUBN
	EW204	N/A	NCDOT 838.01				6.		EXISTING VAULTS, MANHOLES, STORM DRAIN STRUCTURES, VALVE ES, CLEANOUTS, ETC. SHALL BE ADJUSTED AS NEEDED TO MATCH	EPARE <b>) FFIC</b> 2   R 3.812	
	EW206	N/A	NCDOT 838.01				7.	FINIS	HED GRADE. BACKFILL, COMPACTION, SOILS TESTING, ETC. SHALL BE PERFORMED BY	MING PRE <b>NLEIGH O</b> Suite 102 X 919.833	CRIPTION DUA REV.
	EW207	N/A	NCDOT 838.80	CONCRE		L	8.	THE C	OWNER'S INDEPENDENT TESTING LABORATORY. SPOT ELEVATIONS INDICATED ARE AT TOP OF CURB UNLESS NOTED	AWIN <b>RALE</b> Id, Su	ESCR CFPU STOR
	EW209	N/A	NCDOT 838.01	CONCRE	TE ENDWAL	L	9.		RWISE. ALL ELEVATIONS ARE BASED ON VERTICAL DATUM NAVD88. E-CONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO ANY	IS DR I I SY Roa 951 F	DN D PER
	EW210	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L	10.	WOR	K, GRADING OR INSTALLATION OF EROSION CONTROL MEASURES. JANDICAP PARKING SPACES AND STRIPED ACCESSIBILITY AISLES ARE	Trinit 366.4	
	EW212	N/A	NCDOT 838.01	CONCRE	TE ENDWAL	L		TO HA	AVE NO MORE THAN A 1:50 (2.0%) SLOPE IN ALL DIRECTIONS. ALL WALKS ARE TO HAVE NO MORE THAN A 1:20 (5.0%) SLOPE FOR THE	5410	REVIS VER (
	EW300	N/A	NCDOT 838.80	CONCRE	TE ENDWAL	L		LENG	TH OF THE SIDEWALK AND NO MORE THAN A 1:50 (2.0%) SLOPE FOR WIDTH OF THE SIDEWALK.	TEL	HANO
	EW400	N/A	NCDOT 838.80			L	11.	CONT	RACTOR TO IDENTIFY ALL NECESSARY SPILL CURB SECTION TIONS AND INSTALL TO ENSURE POSITIVE DRAINAGE TO STORM	رن ب	
	FE214	N/A					12.	STRU	ICTURES. NTRACTOR NOTICES ANY DISCREPANCIES IN ANY OF THESE SLOPE	OURS.	Z
ON INSET - NOT TO SCALE	FE215 FE301	N/A		D END SEC				REQU	JIREMENTS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT DWNER PRIOR TO POURING ANY CONCRETE SO THAT A SOLUTION CAN	JUGH	
	FE301 FE302	N/A N/A		D END SEC			13.	BE FC		THRC	
	JB105	25.60	NCDOT 840.34 TRAF					POINT	TS BUT IT SHOULD NOT BE ASSUMED THAT ALL NECESSARY SPOT ATIONS ARE SHOWN. DUE TO SPACE LIMITATIONS, THERE MAY BE	EVED	ГЕ 2020 2020
	JB201	20.00	NCDOT 840.34 TRAF					OTHE	ER CRITICAL SPOTS NOT LABELED THAT SHOULD BE TAKEN INTO SIDERATION. THE CONTRACTOR SHALL REVIEW THE GRADING PLAN IN	ACHII	DATE 09/11/2020 09/21/2020
	JB208	23.20	NCDOT 840.34 TRAF	FIC BEARI	NG JUNCTI	ON BOX		DETA	IL AND SHALL ENSURE THAT ALL CRITICAL GRADE POINTS ARE STAKED FOLLOWED TO PROVIDE POSITIVE DRAINAGE.	NOIS	DATE
	JB211	23.00	NCDOT 840.34 TRAF	FIC BEARI	NG JUNCTI	ON BOX	14.	EXIST	TING VEGETATION WITHIN TREE PROTECTIVE AREAS SHALL REMAIN STURBED UNLESS NOTED OTHERWISE. ANY AND ALL LANDSCAPING	JR VIS	09/02/20
23	RS101A	18.50	RISER STRL	ICTURE; S	EE DETAIL			and e	EXISTING TREES AND SHRUBS TO REMAIN WHICH ARE DAMAGED NG DEMOLITION OR CONSTRUCTION SHALL BE REPLACED BY THE	ЛОГ	DRAWN E
	RS202B	18.00	RISER STRU	ICTURE; S	EE DETAIL			CONT	TRACTOR USING A LICENSED LANDSCAPE CONTRACTOR AT NO TIONAL COST TO THE OWNER.		<i>A. MA</i> )
	YI106	22.08	NCDOT 840.14 (	CONCRET	E DROP INL	ET	15.	THE G	GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE CODES IN ERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. THE		DESIGNED
	YI213	18.85	NCDOT 840.18 (	CONCRET	e drop inl	ET		GRAD	DING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES R EACH RAINFALL EVENT OR AS DIRECTED BY THE EROSION CONTROL		B. DOWI
			STORM PIP	F TABLE	:		16.	INSPE	ECTOR OR THE ENGINEER. GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE		CHECKED
		UPSTRE						DISPO	DSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED		R. BAKE
	PIPE #	INVER		SLOPE	LENGTH	DESCRIPTION	17.	OFF-S	SITE STOCKPILES AND/OR WASTE AREAS. CATCH BASINS MUST BE MARKED "DUMP NO WASTE DRAINS TO		SCALE AS SHOV
San	EW-EXPIPE2	14.00		0.47%	7.42 LF	24 inch RCP	17.	STRE	ATCH BASING MOST BE MARKED DOME NO WASTE DRAINS TO AM" OR EQUIVALENT. FRACTOR TO MOVE EXCESS SOIL EXCAVATED FROM STORMWATER		
the second second	EW-EXPIPE1	19.96		0.48%	8.00 LF	24 inch RCP	18.	CONT	ROL MEASURES TO DESIGNED STOCKPILE AREA ON ILM PROPERTY.		11
	101A-101 103-102	14.35 16.35		0.32%	46.59 LF 42.86 LF	18 inch RCP 30 inch RCP		COOF	RDINATE WITH ILM CONTACT ON EXACT LOCATION. REFER TO INSET.		
Contraction of the second seco	105-102	16.93		1.00%	42.00 LF 42.75 LF	30 inch RCP					UU I
	106-105	18.25		1.00%	93.60 LF	24 inch RCP			GRADING PLAN KEYNOTES		Ž
	107-106	21.75		3.00%	89.24 LF	15 inch RCP		CG01	TAPER CURB AND GUTTER TO FULL HEIGHT OVER 10' (TYP.);		I I
	109-108	22.71	22.51	0.30%	68.21 LF	18 inch Class IV RCP		CG03	REFER TO DETAIL CK-135. DAYLIGHT ROOF DRAIN DOWN SPOUTS TO GRADE (TYP.). REFER		Z
````\	201-200	12.89	12.80	0.30%	30.00 LF	30 inch RCP		CG05	TO DETAIL CK-215. STORM CLEANOUT; REFER TO DETAIL CK-210. TRAFFIC RATED IF		0
	202-201	13.05	12.93	0.30%	39.27 LF	30 inch RCP		CG06	WITHIN PAVEMENT (TYP.). ROOF DRAIN SYSTEM, REFER TO PLAN FOR SIZE AND MATERIAL.		<b>⊢</b>  (「) ⊻
2423	204-203	14.55	14.25	1.00%	30.00 LF	42 inch RCP		CG09	MINIMUM COVER OF 2' AND MINIMUM SLOPE OF 1.00%. DAYLIGHT CANOPY DRAINS OUTLET TO GRADE (TYP.)		
	206-205	14.55		1.00%	30.00 LF	42 inch RCP		G23	ADA STALLS (MAX SLOPE 1:50) SIDEWALK (ADA ACCESS ROUTE MAX CROSS SLOPE 1:50; MAX		
	208-207	15.08		1.00%	27.64 LF	30 inch RCP		G24 G30	LONG. SLOPE 1:20) MATCH EXISTING PAVEMENT ELEVATION		이 온 님
	209-208	19.20		0.54%	55.37 LF	30 inch RCP		G31	RIP RAP PAD OVER FILTER FABRIC (REFER TO SIZING CHART)		
	211-210	15.04		1.00% 0.87%	23.73 LF 57.63 LF	42 inch RCP 36 inch RCP		G32 G40	RISER STRUCTURE 24" CONCRETE FLUME		,
	212-211	15.60		0.50%	71.34 LF	30 inch RCP		G41	CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON		
	215-214	19.15		0.30%	47.43 LF	18 inch RCP		G42	EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN). CIRCLE K FUNDED CONSTRUCTION WORK		
	302-301	23.52	23.20	0.35%	92.29 LF	18 inch Class IV RCP		G43	ILM FUNDED CONSTRUCTION WORK		
			\	X 22	6~ \	`\		G44	VARIABLE WIDTH SCM ACCESS EASEMENT		
	21					4	/		RIPRAP SIZING CHART		ן אין אין אין אין אין אין אין אין אין אי
	/		X	/			/ 		• <u>EW101</u> • <u>EW202, 204, &amp; 206</u> CLASS 'B' CLASS 'I'		
WETLANDS			_ 20 / /				_		12'L X 6'W X 18"D 40'L X 22'W X 24"D EW102 FE214		
1,836± SQ. FT. / 0.04± AC. /		/	/\/-				_		CLASS 'B'         CLASS 'A'           16'L X 6'W X 18"D         6'L X 4.5'W X 12"D		
			~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		\ \		~		• <u>EW104</u> • <u>FE301</u> CLASS 'B' CLASS 'A'		
	/		3	\searrow					12'L X 6'W X 18"D 6'L X 4.5'W X 12"D ● EW108 ● FE303		
	20		/		20				CLASS 'A' CLASS 'A' 6'L X 4.5'W X 12"D 8'L X 6'W X 12"D		
			/		V		\ \		• <u>EW200</u> CLASS 'B'		1
			/		K		\ \		18'L X 9'W X 18"D		$ \Sigma $
			A A	<							∣щ∣
			, 'P	```							
~ ~ ~		, , , , , , , , , , , , , , , , , , , ,	/	14			< ,				A N
19	/		/	to .		1 / 1 20 /		+			
18	, 19			/ \	`\ 	\ `	_				JOB NO.
PRELIMINAR	Y - NOT REL	EASED	FOR CONSTR	RUCTIO	N ~	\		D 83	SCALE 1"=40'		37630.0
NSTRUCTION TO BE IN AC						•		NAI			SHEET NO
JTILITY AUTHORITY, NCDE	EQ, AND NC	DOT S	I ANDARDS, SF	'ECIFIC		S, AND DETAILS			0 40' 80'		C3.1



STOCKPILE SITE LOCATION INSET - NOT TO SCALE



1


_____SAN -


_ ____ UGP-----_


____ UGT_____

PRELIMINARY

ALL CONSTRUCTION TO BE IN AC PUBLIC UTILITY AUTHORITY, NCDE









PRIVATE STREET 1 - PLAN VIEW

PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS





GRADING PLAN KEYNOTES							
NUMBER	DESCRIPTION						
	CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE						
G41	SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON						
	EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).						
G42	CIRCLE K FUNDED CONSTRUCTION WORK						
G43	ILM FUNDED CONSTRUCTION WORK						




PRIVATE STREET 1 CROSS SECTION A-A











PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




	GRADING PLAN KEYNOTES
NUMBER	DESCRIPTION
G41	CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).
G42	CIRCLE K FUNDED CONSTRUCTION WORK
G43	ILM FUNDED CONSTRUCTION WORK




PRIVATE STREET 2 CROSS SECTION B-B






09/21/2020

PRIVATE STREET 2 - PLAN VIEW






PHASE IIIA DRY POND **PROFILE VIEW**


PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


Property Owner Certification: "I (We) hereby certify that I (we) am (are) the current owner of the property and that upon receipt of "Authorization-To-Construct" any clearing, grading, construction or development, will be performed in accordance with this plan and that the applicable ordinances and rules of New Hanover County, the State of North Carolina and the Federal Government and its agencies which are hereby made part of this plan. As the owner, I (we) accept full responsibility for the construction and operation and maintenance of the proposed facilities. I (We) will not attempt to transfer of this responsibility without the written authorization of New Hanover County." 09/21/2020 Gum Dil Signature Printed Name and Title: A. Granseur Dick, Facilities Director New Hanover County Airport Authority Date: 09/18/2020 dba Wilmington International Airport DESIGNERS PLAN CERTIFICATION "I HEREBY CERTIFY THAT THIS PLAN HAS BEEN PREPARED IN ACCORDANCE WITH THE LATEST NEW HANOVER COUNTY ORDINANCES AND STORM WATER DESIGN MANUAL AND WITH THE NEW HANOVER COUNTY INTERNATIONAL AIRPORT STORMWATER MASTER PLAN. DRAWING PREPARED / RALEIGH OFFICE oad, Suite 102 | Rale FAX 919 833 8124 SIGNATURE: PRINTED NAME AND TITLE: Stephen Ballentine DATE: 9.17.20 REGISTRATION NUMBER: 26493 iity 495 5410 919.8 9/1 9/2 SCALE 1"=30' DATE 30' 09/02/2020 DRAWN BY A. MAY DESIGNED BY B. DOWNS CHECKED BY R. BAKER SCALE AS SHOWN S <u>JB105</u> TOP 25.60 INV IN 17.5 INV OUT 1 \bigcirc Ζ 30 TON ŰZ RO 25 \square n ▝▐ \square 20 ND Ш U AIRPOR Ŕ \cap 15 \triangleleft ILN PHAS 14+90 $\mathbf{\mathbf{\nabla}}$ PROFILE SCALE C Ц Н \bigcirc JOB NO. 7630.054 SHEET NO. *C3.5*




PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS









PHASE IIIA AND PHASE IIIB STORMWATER NOTES

- PLANS.
- CONSTRUCTION.
- 3
- DRAWINGS, INCLUDING SHOP DRAWINGS FOR ANY PROPOSED MODIFICATION.
- 5. CONTRACTOR TO FINE GRADE ALL POND FINISHED SURFACES TO WITH 2 INCHES +/- TOLERANCE.
- 6. AS-BUILT SURVEY:

THE CONTRACTOR SHALL ACCURATELY CONSTRUCT ALL SCM GRADES, BERM, SPILLWAY, RISER TOP, RISER INVERTS, ETC. WITHIN ± 0.2 FEET VERTICALLY OF THE APPROVED PLANS. AT THE END OF THE PROJECT, THE CONTRACTOR SHALL AS-BUILT SURVEY ALL FEATURES OF THE SCM BY A LICENSED SURVEYOR. SUBMIT SEALED AS-BUILT SURVEY AND CAD FILE TO THE ENGINEER. THE ENGINEER WILL THEN COORDINATE ANY ADJUSTMENTS NEEDED WITH THE CONTRACTOR AND CERTIFICATION WITH THE MUNICIPALITY. ADDITIONAL AS-BUILT SURVEYS MAY BE NEEDED BASED ON REQUIRED ADJUSTMENTS.

DRY DETENTION BASIN SPECIFICATIONS:

- 3. THE RISER STRUCTURE HAS BEEN DESIGNED WITH A CONCRETE ANCHOR FOR ANTI-FLOATATION.
- RISER.
- FOR MAINTENANCE.
- 7. THE RISER SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RISER DETAIL.

10. REFER TO CONVERSION SEQUENCE ON THIS SHEET

DRY DETENTION BASIN CONVERSION SEQUENCE:

- CONVERSION SHOULD ONLY REQUIRED REMOVAL OF SEDIMENT AND MINOR DRESS-UP WORK.
- TO BEGINNING THE CONVERSION.

- FABRIC, AND LOW FLOW CHANNEL PER SCM DETAILS.

- 9 BEEN COMPLETED:
 - OPERATION & MAINTENANCE AGREEMENT IS COMPLETE.

BERM EMBANKMENT AND SOIL COMPACTION SPECIFICATIONS

- ACCORDANCE WITH ASTM D698.
- TO COMPACTION.
- 3. CONFORMING TO SPECIFIED REQUIREMENTS SHALL BE REMOVED AND REPLACED WITH ACCEPTABLE MATERIALS.
- OF THE NEXT SOIL LIFT.
- 5. SURFACE WATER AND STREAM FLOW SHALL BE CONTINUOUSLY CONTROLLED THROUGHOUT CONSTRUCTION AND THE PLACEMENT OF CONTROLLED FILL. 6.
- AN ATTEMPT TO STABILIZE ANY PORTIONS OF THE FOUNDATION SOILS WITH CRUSHED STONE.
- DOCUMENTED BY THE GEOTECHNICAL ENGINEER.
- 9. COMPACTORS OR MINIATURE SELF-PROPELLED ROLLERS.
- 10. COMPACTION BY MEANS OF DROP WEIGHTS FROM A CRANE OR HOIST SHALL NOT BE PERMITTED.
- 12. INSTALL CLAY LINER PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- TEMPORARILY SEEDED AND MULCHED OR HYDROSEEDED WITH NON-CLUMPING TURF GRASS.
- 14. NO TREES OR WOODY VEGETATION ARE ALLOWED TO BE PLANTED ON THE DAM OR EMBANKMENT

PRELIMINARY - NOT RELEASED FOR CONSTRUCTION

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

1. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DESIGN ENGINEER OF ANY DISCREPANCIES FOUND WITHIN THE

2. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE ON-SITE GEOTECHNICAL ENGINEER FOR OBSERVATION, TESTING AND CERTIFICATION OF

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH NCDEQ STANDARDS, NEW HANOVER COUNTY, THE WILMINGTON INTERNATIONAL AIRPORT STORMWATER MASTER PLAN, AND THE PROPOSED STORMWATER MANAGEMENT FACILITY DETAILS AND SPECIFICATIONS SHOWN IN THESE DRAWINGS.

4. SOILS, COMPACTION AND/OR OTHER MISCELLANEOUS DETAILS AND SPECIFICATIONS MAY BE MODIFIED PER THE RECOMMENDATIONS OF THE ON-SITE GEOTECHNICAL ENGINEER. HOWEVER, PRIOR TO IMPLEMENTATION, THE DESIGN ENGINEER SHALL BE NOTIFIED OF ANY DEVIATION FROM THESE DESIGN

1. THE DRY DETENTION BASIN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ILM STORMWATER MASTER PLAN, NCDEQ AND THE PROPOSED STORMWATER MANAGEMENT FACILITY DETAILS AND SPECIFICATIONS SHOWN IN THESE DRAWINGS.

2. ALL SIDE SLOPES AND BASIN FLOOR SHALL BE PERMANENTLY STABILIZED WITH A DENSE STAND OF GRASS.

4. A TRASH RACK IS REQUIRED AT THE TOP OF THE RISER, IT SHOULD BE INSTALLED TO PROVIDE ACCESS ALIGNED WITH THE STEPS ON THE BERM SIDE OF THE

5. AN INVERTED SIPHON AND A CONCRETE PLUNGE POOL HAVE BEEN DESIGNED AT THE RISER ORIFICE TO REDUCE THE LIKELIHOOD OF CLOGGING, AND ALLOW

6. THE DRY DETENTION BASIN SHALL BE GRADED IN ACCORDANCE WITH THE APPROVED PLANS, SECTIONS AND DETAILS.

8. THE EMERGENCY SPILLWAY SHALL BE LINED WITH RIPRAP. REFER TO DETAIL ON THE APPROVED PLANS.

9. THE OWNER'S GEOTECHNICAL ENGINEER SHALL OVERSEE THE INSTALLATION OF THE BERM, TO PROVIDE BERM COMPACTION TESTING.

DRY DETENTION BASIN WILL INITIALLY BE INSTALLED AS A SKIMMER SEDIMENT BASIN. REFER TO GRADING PLAN AND DRY DETENTION BASIN SECTIONS AND DETAILS FOR FINAL STAGE. THE FINAL BASIN AND BERM GRADING SHOULD HAVE BEEN PERFORMED AS PART OF THE EROSION CONTROL PHASE 1 AND

2. STABILIZE ALL AREAS TRIBUTARY TO THE DRY DETENTION BASIN AND OBTAIN APPROVAL FROM THE NCDEQ AND NEW HANOVER COUNTY INSPECTOR PRIOR

3. LEAVE SKIMMER IN PLACE, REMOVE BAFFLES AND SEDIMENT FROM THE BOTTOM OF THE BASIN. FINE GRADE BERM AS REQUIRED.

4. INSTALL TRASH RACK, REMOVE SKIMMER, AND INSTALL PERMANENT ORIFICE PIPE AS SHOWN ON THE APPROVED PLANS

5. INSTALL CONCRETE PLUNGE POOL BENEATH PERMANENT ORIFICE AS SHOWN ON THE APPROVED PLANS. INSTALL CLAY LINER, TOPSOIL, RIP-RAP, FILTER

6. REPAIR SPILLWAY RIPRAP LINER AS NEEDED AND SEED ALL DISTURBED AREAS.

7. SUBMIT SURVEY CAD FILE WITH SPOT GRADES TO ENGINEER FOR REVIEW. CONTACT ENGINEER TO SCHEDULE INSPECTION.

8. MAKE ANY ADJUSTMENTS REQUIRED BY ENGINEER FOLLOWING INSPECTION AND REVIEW OF AS-BUILT SURVEY DATA.

CONVERSION OF THE SKIMMER BASIN TO A PERMANENT DRY DETENTION BASIN SHALL NOT BE CONSIDERED COMPLETE UNTIL THE FOLLOWING ITEMS HAVE

• BASIN HAS BEEN FULLY CONVERTED AND IS BUILT IN ACCORDANCE WITH THE APPROVED DESIGN, AS DETERMINED BY THE ENGINEER.

• NCDEQ HAS PERFORMED AN INSPECTION AND APPROVED THE COMPLETED DRY DETENTION BASIN, AND THE AS-BUILTS.

CONTROLLED FILL, AS SPECIFIED BY THE GEOTECHNICAL ENGINEER. IN THE BERM EMBANKMENT /KEY TRENCH SHALL BE PLACED IN 6-INCH LOOSE LAYERS (3-INCH LOOSE LAYERS WITHIN 3-FEET OF EITHER SIDE OF THE PRINCIPAL SPILLWAY PIPE TO A DEPTH OF 2-FEET OVER THE PIPE) AND SHALL BE COMPACTED TO A DENSITY OF NO LESS THAN 95% OF THE STANDARD PROCTOR MAXIMUM DENSITY AT A MOISTURE CONTENT OF + OR - TWO PERCENTAGE POINTS OF THE OPTIMUM MOISTURE CONTENT IN

ALL VISIBLE ORGANIC DEBRIS SUCH AS ROOTS AND LIMBS SHALL BE REMOVED FROM THE FILL MATERIAL PRIOR TO COMPACTION TO THE REQUIRED DENSITY. SOILS WITH ORGANIC MATTER CONTENT EXCEEDING 5% BY WEIGHT SHALL NOT BE USED. STONES GREATER THAN 3-INCH (IN ANY DIRECTION) SHALL BE REMOVED FROM THE FILL PRIOR

FILL MATERIAL PLACED AT DENSITIES LOWER THAN SPECIFIED MINIMUM DENSITIES OR AT MOISTURE CONTENTS OUTSIDE THE SPECIFIED RANGES OR OTHERWISE NOT

4. ANY FILL LAYER THAT IS SMOOTH DRUM ROLLED TO REDUCE MOISTURE PENETRATION DURING A STORM EVENT SHALL BE PROPERLY SCARIFIED PRIOR TO THE PLACEMENT

FOUNDATION AREAS MAY REQUIRE UNDERCUTTING OF COMPRESSIBLE AND/OR UNSUITABLE SOILS IN ADDITION TO THAT INDICATED ON THE PLANS. ALL SUCH UNDERCUTTING SHALL BE PERFORMED AT THE DISCRETION OF THE GEOTECHNICAL ENGINEER AND SHALL BE MONITORED AND DOCUMENTED. IN NO CASE SHALL THERE BE

TREATMENT OF SEEPAGE AREAS, SUBGRADE PREPARATION, FOUNDATION DEWATERING AND ROCK FOUNDATION PREPARATION (I.E., TREATMENT WITH SLUSH GROUTING, DENTAL CONCRETE, ETC.) MAY BE REQUIRED AT THE DISCRETION OF THE GEOTECHNICAL ENGINEER. ALL SUCH ACTIVITIES SHALL BE CLOSELY MONITORED AND

8. FILL ADJACENT TO THE RISER AND PRINCIPAL SPILLWAY PIPE SHALL BE PLACED SO THAT LIFTS ARE AT THE SAME LEVEL ON BOTH SIDES OF THE STRUCTURES.

EARTHWORK COMPACTION WITHIN 3-FEET OF ANY STRUCTURES SHALL BE ACCOMPLISHED BY MEANS OF HAND TAMPERS, MANUALLY DIRECTED POWER TAMPERS OR PLATE

11. HEAVY EQUIPMENT SHALL NOT BE ALLOWED TO PASS OVER CAST-IN-PLACE STRUCTURES (INCLUDING THE CRADLE) UNTIL ADEQUATE CURING TIME HAS ELAPSED.

13. TO RE-ESTABLISH VEGETATION AFTER CONSTRUCTION, A 2- TO 3-INCH LAYER OF TOPSOIL SHALL BE PLACED ON THE DISTURBED EMBANKMENT SURFACE AND THE AREA

२	SEAL D22530 W. BAYHILI O9/21/2020						
٦	THIS DRAWING PREPARED AT THE RALEIGH OFFICE 5410 Trinity Road, Suite 102 Raleigh, NC 27607 TEL 919.866.4951 FAX 919.833.8124 www.timmons.com	REVISION DESCRIPTION	REVISION PER CFPUA REVIEW	HANOVER COUNTY STORMWATER SUBMITTAL			
	YOUR VISION ACHIEVED THROUGH OURS.	DATE	09/11/2020				
	YOUR VISI	C		DATE 02/2 RAWN	2020)	
			DES	. MA IGNE DOV	D BY	,	
				ECKEI BAK			
		A		SCAL SHC		1	
		т Т (but not
	TIR ROBANG CORPORATION CONTRACTOR CONTACTOR CONTRACTOR				D.		ese plans and associated documents are the exclusive property of TIMMONS GROUP and may not be reproduced in whole or in part and shall not be used for any purpose whatsoever, inclusive, but not
		37	SF	30. IEET I C3.	NO.	54	hese plans and as

SKIMMER SEDIMENT BASIN MAINTENANCE

INSPECT SKIMMER SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO ONE SIDE SO THAT THE SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SURE VEGETATION GROWING IN THE BOTTOM OF THE BASIN DOES NOT HOLD DOWN THE SKIMMER. REPAIR BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM. IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK, PULL THE SKIMMER OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS. ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IF IT IS CLOGGED; IF SO REMOVE THE DEBRIS. IF THE SKIMMER ARM OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER. CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL AREAS. FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.

BAFFLES MAINTENANCE

INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY. BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR

BECOME INEFFECTIVE, REPLACE IT PROMPTLY. REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL, TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES. TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEANOUT, AND REPLACE IF DAMAGED DURING CLEANOUT OPERATIONS. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH. AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED, REMOVE ALL BAFFLE MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, BRING THE AREA TO GRADE, AND STABILIZE IT.




INV=16.52


INV=13.57-

- OWNER/DEVELOPER/CONTRACTOR SHALL OBTAIN A COPY OF THE APPROVED EROSION CONTROL PLAN AND MAINTAIN A COPY OF THE PLAN ON SITE THROUGHOUT DURATION OF CONSTRUCTION.
- OWNER/CONTRACTOR SHALL NOTIFY NEW HANOVER COUNTY A MINIMUM OF 72


ENFORCEMENT OFFICER, OR OTHER GOVERNING AGENCY.

- HOURS BEFORE START OF CONSTRUCTION ON EACH PHASE. ONLY CLEAR/GRADE ENOUGH TO INSTALL SEDIMENT CONTROL DEVICES AS SHOWN IN PHASE I
- INSTALL CONSTRUCTION ENTRANCE, PIPES, TEMPORARY DIVERSION DITCHES CHECK DAMS, AND TEMPORARY INLET PROTECTION AS INDICATED ON PLAN. INSTALL SILT FENCE, SILT FENCE OUTLETS AROUND THE PERIMETER OF THE SITE. DISTURB ONLY THE AREAS NECESSARY FOR INSTALLATION.
- ADJUST EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY FOR PROPER OPERATION. INSTALL ADDITIONAL EROSION CONTROL MEASURES IF DETERMINED NECESSARY BY INSPECTOR
- INSPECT ALL EROSION CONTROL DEVICES AFTER EVERY RAINFALL EVENT AND AT LEAST ONCE PER WEEK. REPAIR AND CLEAN OUT AS REQUIRED. NOTIFY NEW HANOVER COUNTY FOR AN INSPECTION AFTER THIS IS
- COMPLETED. PROCEED TO PHASE 2 OF THE EROSION CONTROL SEQUENCE WHEN PHASE 1
- MEASURES HAVE BEEN COMPLETED, INSPECTED, AND APPROVED.





	GENERAL EROSION AND SEDIMENT CONTROL NOTES:		
E I KEYNOTES	1. ALL CONSTRUCTION SHALL COMPLY WITH NEW HANOVER COUNTY STANDARDS AND SPECIFICATIONS.		ARO
	2. A COPY OF THE APPROVED EROSION CONTROL PLAN MUST BE ON FILE AT THE JOB SITE	IN OFFES	STON STATE
(TYP.)	AT ALL TIMES. 3. FAILURE TO FOLLOW THE APPROVED PLAN SEQUENCE AND DETAILS COULD SUBJECT	SEA 2225	
ENTRANCE; REFER TO	 THE CONTRACTOR TO FINES AND PENALTIES ISSUED BY DEQ. 4. FIELD VERIFY ALL DIMENSIONS AND GRADES ON THESE PLANS PRIOR TO 	0225	30
	4. FIELD VERIFY ALL DIMENSIONS AND GRADES ON THESE PLANS PRIOR TO CONSTRUCTION. FAILURE TO NOTIFY THE OWNER OF ANY DISCREPANCIES PRIOR TO	F CZ WGIN	EFROM
R TO DETAIL (TYP.)	PROCEEDING WITH PLAN OR GRADE CHANGES, MAY RESULT IN NO EXTRA	VIIIAD W.	BAKKI
37 AC	COMPENSATION PAID TO THE CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY.		09/21/2020
STORAGE=7,866 CF	5. EXCAVATION AND EARTH MOVING OPERATIONS SHALL BE CONDUCTED UNDER THE		
V'D STORAGE=20,670 CF	 SUPERVISION OF THE GEOTECHNICAL ENGINEER. 6. VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. EXISTING 		
UME) TICE ON	UTILITIES SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND FROM A SURVEY OF	E	
M	ABOVE GROUND FEATURES. NO WARRANTY IS GIVEN OR IMPLIED AS TO THE ACCURACY OF THE INFORMATION. ALL EXISTING UTILITIES SHOULD BE CONSIDERED APPROXIMATE	-7 s.com	
	IN LOCATION AND VERIFIED PRIOR TO COMMENCING ACTIVITY ON SITE.	27607 Imons.	
NC; S = 1.6%	7. ALL ADJACENT ROADS TO THE SITE ARE TO BE SWEPT AND WASHED AT THE END OF EACH WORK DAY TO ENSURE NO SEDIMENT COLLECTS ON THE ROADWAYS.	· · · >	V SUBMITTAI
	8. INSPECT AND PROPERLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES		IW
	WEEKLY AND AFTER EVERY RAINFALL EVENT. 9. INSTALL ANY ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT	· U	
	SEDIMENT RUNOFF.	tEPARED OFFICE 02 Ral 33.8124	
	10. PROVIDE NEW HANOVER COUNTY WITH THE LOCATION OF OFFSITE STOCKPILES USED TO STORE EXCAVATED SOIL FROM THE SITE. THE LOCATION OF OFFSITE STOCKPILES		REVISION DESCRIPTION REVISION PER CFPUA REVIEW DVER COUNTY STORMWATER S
AC; S = 1.8%	MUST BE AN UPLAND AREA. IF AN OFFSITE BORROW OR SPOIL SITE IS UTILIZED, THEN		A R MW
	THE DISTURBED AREA FOR THE BORROW/SPOIL SITE MUST BE INCLUDED IN THE LAND DISTURBANCE PERMIT. THE CONTRACTOR WILL PROVIDE THE LOCATION OF ALL	MING F NLEIGH Suite X 919	SCR ORI
	EXCAVATED SOILS USED FOR THIS PROJECT TO NEW HANOVER COUNTY. THIS AREA	<u>w</u> – w –	ST ST
	MUST ALSO BE AN UPLAND AREA. 10.1. CONTRACTOR TO MOVE EXCESS SOIL EXCAVATED FROM STORMWATER CONTROL	THIS D 5410 Trinity Ro 919.866.4951	ISION ION PEF
	MEASURES TO DESIGNED STOCKPILE AREA ON ILM PROPERTY. CORRDINATE WITH	THIS Trinity 866.495	REVISION VISION PE ER COUNTY
& NON-WOVEN LINER	ILM CONTACT ON EXACT LOCATION.	10 T 9.86	ISI CC
	11. CONCRETE WASHOUT TO BE LOCATED A MINIMUM OF 50' FROM ANY DRAINAGE STRUCTURE.	541	REV R
	12. THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS.	Ë	RE REVI ANOVER
X 6.5'W X 12"D)	13. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER,		
X 5.3'W X 12"D)	ENFORCEMENT OFFICER, OR OTHER GOVERNING AGENCY.	<u>v</u>	
(4.5'W X 12"D)	PHASE I EROSION CONTROL CONSTRUCTION SEQUENCE:	YOUR VISION ACHIEVED THROUGH OURS	
	1. OWNER/DEVELOPER/CONTRACTOR SHALL OBTAIN A COPY OF THE APPROVED	HB	
LINE DELINEATES THE	EROSION CONTROL PLAN AND MAINTAIN A COPY OF THE PLAN ON SITE	no	
E PRIMARY WORK ON	THROUGHOUT DURATION OF CONSTRUCTION.	H H	
UTILITY PLAN).	2. OWNER/CONTRACTOR SHALL NOTIFY NEW HANOVER COUNTY A MINIMUM OF 72 HOURS BEFORE START OF CONSTRUCTION ON EACH PHASE.	Ē	DATE 09/11/2020 09/21/2020
RK	3. ONLY CLEAR/GRADE ENOUGH TO INSTALL SEDIMENT CONTROL DEVICES AS	IEV	TE
	SHOWN IN PHASE I. 4. INSTALL CONSTRUCTION ENTRANCE, PIPES, TEMPORARY DIVERSION DITCHES,	ACH	DA 0/11
	4. INSTALL CONSTRUCTION ENTRANCE, PIPES, TEMPORARY DIVERSION DITCHES, CHECK DAMS, AND TEMPORARY INLET PROTECTION AS INDICATED ON PLAN.	NO	50 50
	INSTALL SILT FENCE, SILT FENCE OUTLETS AROUND THE PERIMETER OF THE	ISI	DATE
	SITE. DISTURB ONLY THE AREAS NECESSARY FOR INSTALLATION. 5. ADJUST EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY FOR	Х <	09/02/2020
	PROPER OPERATION. INSTALL ADDITIONAL EROSION CONTROL MEASURES IF	лол	
	DETERMINED NECESSARY BY INSPECTOR.		DRAWN BY
	 INSPECT ALL EROSION CONTROL DEVICES AFTER EVERY RAINFALL EVENT AND AT LEAST ONCE PER WEEK. REPAIR AND CLEAN OUT AS REQUIRED. 		A. MAY
	7. NOTIFY NEW HANOVER COUNTY FOR AN INSPECTION AFTER THIS IS		DESIGNED BY
			B. DOWNS
	 PROCEED TO PHASE 2 OF THE EROSION CONTROL SEQUENCE WHEN PHASE 1 MEASURES HAVE BEEN COMPLETED, INSPECTED, AND APPROVED. 		
			CHECKED BY
			R. BAKER
			SCALE
			AS SHOWN
			L
-			Г О
<		•	
		•	



PERMANENT DIVERSION DITCH TEMPORARY DIVERSION DITCH SILT FENCE STONE OUTLET EMERGENCY SPILLWAY / RIP RAP 00000 APRON CHECK DAM

40'


CONSTRUCTION ENTRANCE TEMPORARY INLET PROTECTION


CONCRETE WASHOUT

HORSESHOE INLET PROTECTION SKIMMER

 \bigcirc Z

Ζ





PHASE II EROSION CONTROL CONSTRUCTION SEQUENCE:

- 24 - - - - - - - - - - 3

-SAN -

_____ UGP____ _ _ _ _ _

RIM=21.59

INV(N)=13.27

INV(S)=13.04

GAS LINE DRAWN FROM NCDOT PLANS

(EXIST

MAINTAIN ALL EXISTING EROSION CONTROL FEATURES PREVIOUSLY CONSTRUCTED AND ASSOCIATED WITH PHASE 2 EROSION C CONTINUE BRINGING FILL INTO THE SITE. IMPORTED MATERIAL WILL REQUIRE A PERMITTED SITE APPROVAL BEFORE THIS PROCE SHALL BE BROUGHT INTO THE SITE AND EVENLY SPREAD OUT THROUGH THE SITE AS SHOWN IN LIFTS OF NO MORE THAT 1.0' AT ROLL COMPACTED BY A DOZER OR EQUIVALENT AS IT IS PLACED.

BEGIN INSTALLATION OF THE STORM PIPE SYSTEM FROM OUTLET POINT (LOW END) AND WORK UPSTREAM. PIPE INLET PROTECT UTILIZED AT THE END OF EACH WO

INSTALL SITE IMPROVEMENTS, STORMWATER DRAINAGE SYSTEM, UTILITY SERVICES, SIDEWALKS AND DRIVES AS SHOWN ON THE ALL OPEN TRENCHES FOR UTILITY AND STORMWATER INSTALLATION SHALL BE PROTECTED FROM SEDIMENTATION BY PILING EXC ON THE UPHILL SIDE OF EXCAVATION.

5. INSTALL ADEQUATE EROSION AND SEDIMENT CONTROL MEASURES AND/OR INCREASE MAINTENANCE FREQUENCY WHERE APPRC TO PREVENT ACCELERATED EROSION, OFF-SITE SEDIMENTATION, OR REPETITIVE NON-COMPLIANCE ISSUES. ALL MEASURES MUS PLAN DETAIL. ENSURE CONSTRUCTION TRAFFIC IS LIMITED TO THE CONSTRUCTION ENTRANCE ONLY.

- GROUND COVER SHALL BE PROVIDED AS FOLLOWS: FOR ALL AREAS OF MODERATE AND/OR STEEP SLOPES, PROVIDE TEMPORARY GROUND COVER IF THE SLOPE HAS NOT BE A PERIOD OF FOURTEEN (14) DAYS. SLOPES GREATER THAN 3:1 REQUIRE GROUND COVER IN 7 DAYS.
 - PROVIDE GROUND COVER SUFFICIENT TO RESTRAIN EROSION ON ANY PORTION OF THE SITE UPON WHICH FURTHER LAND ACTIVITY IS NOT BEING UNDERTAKEN WITHIN FOURTEEN (14) CALENDAR DAYS OF TEMPORARILY OR PERMANENTLY SUSPE DISTURBING ACTIVITY.
- ESTABLISH PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION WITHIN FOURTEEN (14) CALENDAR DAYS FOL COMPLETION OF CONSTRUCTION OR DEVELOPMENT AND/OR PRIOR TO FINAL INSPECTION. INSTALL CURB & GUTTER AND GRAVEL BASE.
- 8 9. MODIFICATIONS TO THE APPROVED AND PERMITTED PLANS SHALL BE APPROVED BY EROSION CONTROL INSPECTIONS PRIOR TO REMO
- INSTALLATION. CONTACT THE EROSION CONTROL INSPECTOR TO OBTAIN SIGN-OFF ON THE PLANS. 10. MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES IN GOOD WORKING ORDER. SILT FENCE, INLET PROTECTION, AND C MEASURES MUST BE CLEANED OUT BEFORE THEY ARE HALF FULL. CLOGGED STONE FILTERS MUST BE REFRESHED/REPLACED. S HAVE HOLES OR TEARS.
- 11. AT A MINIMUM OF SEVEN (7) DAYS PRIOR TO SCHEDULING THE STORMWATER FINAL INSPECTION, SUBMIT ANY REQUIRED PAPERW EROSION CONTROL INSPECTORS FOR APPROVAL. FAILURE TO DO SO WILL PREVENT A CERTIFICATE OF OCCUPANCY FROM BEING 12. ONCE THE STORMWATER FINAL INSPECTION IS APPROVED, CLOSE THE GRADING PERMIT AND OBTAIN A CERTIFICATE OF COMPLE

SKIMMER SEDIMENT BASIN MAINTENANCE

INSPECT SKIMMER SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EA INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOV RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT AG ONE-HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO C SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIM BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SUI GROWING IN THE BOTTOM OF THE BASIN DOES NOT HOLD DOWN THE S BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS OR AROUND THEM. IF THE SKIMMER IS CLOGGED WITH TRASH AND THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK, OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS. ALSO CHE THE SKIMMER TO SEE IF IT IS CLOGGED; IF SO REMOVE THE DEBRIS. IF BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OB WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND BEFORE REPOSITIONING THE SKIMMER. CHECK THE FABRIC LINED SPIL MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIL CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAM EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY RE REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL P TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WIT


BAFFLES MAINTENANCE

· _ _ .

.836± SQ. F 0.04± AC.


INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. REPAIRS IMMEDIATELY. BE SURE TO MAINTAIN ACCESS TO THE BAFFLES OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR

BECOME INEFFECTIVE, REPLACE IT PROMPTLY. REMOVE SEDIMENT DEF REACHES HALF FULL, TO PROVIDE ADEQUATE STORAGE VOLUME FOR REDUCE PRESSURE ON THE BAFFLES. TAKE CARE TO AVOID DAMAGING CLEANOUT, AND REPLACE IF DAMAGED DURING CLEANOUT OPERATION SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH. AFTER DRAINAGE AREA HAS BEEN PROPERLY STABILIZED, REMOVE ALL BAFF UNSTABLE SEDIMENT DEPOSITS, BRING THE AREA TO GRADE, AND STA




PRELIMINARY - NOT RELEASED FOR CONSTRUCTION ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUN PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

		GE		ROSION AND SEDIMENT CONTROL NOTES:		
 A mer of the start of the start	CONTROL. CESS BEGINS. ALL FILL	1.			WITH CA	ROJUL
	T A TIME. FILL SHALL BE	2.	A COPY OF T	HE APPROVED EROSION CONTROL PLAN MUST BE ON FILE AT THE JOB SITE	11 NO FESS	TON THE
	TION SHALL BE	3.	FAILURE TO	FOLLOW THE APPROVED PLAN SEQUENCE AND DETAILS COULD SUBJECT	SEA 0225	30
	HE APPROVED PLANS. EXCAVATED MATERIAL	4.	CONSTRUCT	ION. FAILURE TO NOTIFY THE OWNER OF ANY DISCREPANCIES PRIOR TO	F CAN WGIN	ER BOOM
	ROVED MEASURES FAIL		COMPENSAT	ION PAID TO THE CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS		BAKLIN
	UST BE INSTALLED PER	5.	EXCAVATION	AND EARTH MOVING OPERATIONS SHALL BE CONDUCTED UNDER THE	(39/21/20-0
 And M. Ander M. A	BEEN DISTURBED FOR	6.	VERIFY THE	LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. EXISTING		
 Services Services<	ND-DISTURBING		ABOVE GROU	JND FEATURES. NO WARRANTY IS GIVEN OR IMPLIED AS TO THE ACCURACY	07 s.com	
 Services Services<	PENDING LAND	7.	ALL ADJACE	NT ROADS TO THE SITE ARE TO BE SWEPT AND WASHED AT THE END OF	: 2760 nmon	
 Services Services<	OLLOWING	8.	INSPECT AND	O PROPERLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES	T THE th, NC ww.tir	LLIW.
 PICH TOTAL 	MOVAL OR	9.	INSTALL ANY	ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT	<u> </u>	
 PICH TOTAL 	OTHER SIMILAR	10.	PROVIDE NE	W HANOVER COUNTY WITH THE LOCATION OF OFFSITE STOCKPILES USED	KEPAR OFFI 02 33.81.	ION
 PICH TOTAL 	SILT FENCE CAN NOT		MUST BE AN	UPLAND AREA. IF AN OFFSITE BORROW OR SPOIL SITE IS UTILIZED, THEN	NG PF EIGH uite 1 919.8:	RIPT UA R RMW/
 PICH TOTAL 	RWORK TO THE NG ISSUED.		DISTURBANC	E PERMIT. THE CONTRACTOR WILL PROVIDE THE LOCATION OF ALL	<u>н</u> , , , ,	R CFP
• • • • • • • • • • • • • • •	LETION.	10	.1. CONTRA	ACTOR TO MOVE EXCESS SOIL EXCAVATED FROM STORMWATER CONTROL	HIS D nity Rc 4951	
• • • • • • • • • • • • • • •			ILM CON	ITACT ON EXACT LOCATION.	T 0 Trin .866.	EVIS
 Province Prevent Advisorial Monta Prevent<td></td><td></td><td>STRUCTURE</td><td></td><td></td><td>DVE </td>			STRUCTURE			DVE
 Andre Store Store Andre Store Stor			REQUIREMEN	NTS.	Ш. Н	HANG
 Andre Store Store Andre Store Stor	ACH SIGNIFICANT (1/2	13.			ss.	NEW
Index and Insert and Index and	ACCUMULATES TO		NUMBER	DESCRIPTION	INO H	$ ^{-} $
Index and Insert and Index and	MENT FROM THE ENTIRE	F			SOUG	
Index and Insert and Index and	SKIMMER. REPAIR			SILT FENCE OUTLET; REFER TO DETAIL (TYP.)	D THF	
Index and Insert and Index and	IS FLOWING UNDERNEATH ERE IS WATER IN THE			DETAIL	IIEVEI	АТЕ 1/202 1/202
Index and Insert and Index and	3 UP AND DOWN AND I, PULL THE SKIMMER	-	EC205		I ACH	DA 09/11 09/21
Index and Insert and Index and	ECK THE ORIFICE INSIDE F THE SKIMMER ARM OR			DRAINAGE AREA= 2.24 AC; S = 1.6%	ISION	
Index and Insert and Index and	BSTRUCTION CLEARED		EC206	D10=1.0'; T=0.97 #/SF	UR V.	09/02/2020
MARE, AND HOPECT THE DATE, AND HOPECT THE CONTROL AND HOPECT THE DOTATIONS SHOULD BE INTO CONTROL AND TO FRECAUTIONS SHOULD BE LINK WY AND TO ESS SHOULD HE FARME PERSIAMENT DEFINITION SOUTH AND TO ESS SHOULD HE FARME DEFINITION SAUTIONS SHOULD BE LINK WY AND TO ESS SHOULD HE FARME DEFINITION SAUTIONS SHOULD BE LINK WY AND TO ESS SHOULD HE FARME DEFINITION SAUTIONS SHOULD BE LINK WY AND TO EDD AND TO CONTROL BE CO		-		LINE W/ N. AMERICAN GREEN (S75)	λO	DRAWN BY
LANCES PRECING INFO: LANCE ANY REQUIRED SOUCH THE CARE AND CONTROL TO COMP WILL SAME UNCOME THE CONTROL TO COMP WILL SAME UNCOME AND CONTROL TO COMP WILL SAME UNCOME AND CONTROL TO COMP WILL SAME COMP WILL SAME POSITS WHEN IT THE CONTROL TO WHEN AND TO THE CONTROL TO WHEN AND TO THE TARK THE AND TO WHEN AND TO THE CONTROL TO WHEN AND TO WHEN AND TO THE AND THE AND TO WHEN AND TO THE AND T				DRAINAGE AREA= 0.24 AC; S = 4.1%		A. MAY
LINECE. LUNC KW N AMERICAN GREEN (\$75) UNCLUE W LINEC AVY REQUIRED SEVENT TO WERE AND TO UNE SIGN DIFFORMATION OF A 450 TO THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF A 450 THE EXTENSION OF TO HAR DIVERSION DIFFORMATION OF A 450 THE EXTENSION OF A 450 THE EXTENSION OF A 450 THE A 450 THE A 450 THE DIVERSION A DIFFORMATION OF A 450 THE A 450 THE A 450 THE A 450 THE DIFFORMATION OF A 450 THE A 450 THE DIFFORMATION OF A 450 THE			EC207	D10=0.5'; T=1.28 #/SF		
EARLE AVY RECURRED SOUCH THE AVAILABLE CONTRUCTING EC320 COLORS OF SUICE 227 COLORS AVAILABLE EC320 COLORS AVEL COLORS AV				LINE W/ N. AMERICAN GREEN (S75)		
ESCRETURATE THE CONTROL THE FARING POSITIS WITHINT THE MAX TRANK MOTION IN SECURITY CARLES TO UP OF THE WAS IS SIDES LIVE WIN A MERCINA GREEN (S73) THE WAS TRANK MOTION IN SECURITY OF THE CONTROL THE ACCESS IN THE PERMANENT DEPENDING THE ACCESS IN THE BECAUSE OF THE INFORMATION OF THE INFORMATION OF THE ACCESS IN THE CONTROL THE INFORMATION OF THE INFORMATION OF THE INFORMATION IN SECURITY OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION IN SECURITY OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION IN SECURITY OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE INFORMATION OF THE INFORMATION INFORMATION OF THE INFORMATION OF THE				DRAINAGE AREA= 0.70 AC; S = 0.8%		
POSITION WITCH THE NEXT RAIN AND TO THE BAPFLES DURING SEDURING TO THE BAPFLES DURING TO SEDURING TO THE SEDURING TO SEDURING TO SEDURIN	ES. SHOULD THE FABRIC		EC208	D10=0.75'; T=0.4 #/SF		
G THE BAFFLES DURING THE DEFTH THE CONTRIGUTING LEW METRIX S AND BOULDET IN BAUNDEZ HEL AT CREW (VO 22) FPS DIG 1, 17 CF3, VO 22) FPS DIG 1, 17 CF3,	EPOSITS WHEN IT			LINE W/ N. AMERICAN GREEN (S75)	•	
RTHE CONTRIGUTING RELATERALS AND BALLET II. IND BALLET II. II. IND BALLET II. IND BALLET II. IND	G THE BAFFLES DURING			DRAINAGE AREA= 1.06 AC; S = 1.1%		
USE DO PORTUGANCE SEND SIND	R THE CONTRIBUTING		EC209	D10=1.0'; T=0.7 #/SF	•	
IND DRAINAGE AREA-153 AC; 8-0.3% IND BC200 COUNT.17, CFS, VIT-228 FPS UNE WIN AMERICAN GREEN (\$75) DIO-15; T-0.31 #SF UNE WIN AMERICAN GREEN (\$75) DIO-15; T-0.31 #SF ERSION DITCH DRAINAGE AREA-122 AC; S-0.7%, S ERSION DITCH DRAINAGE AREA-123 AC; S-1.80% END DRAINAGE AREA-123 AC; S-1.80% UNE WIN AMERICAN GREEN (\$75) DRAINAGE AREA-123 AC; S-1.80% EC210 DRAINAGE AREA-123 AC; S-1.80% UNE WIN AMERICAN GREEN (\$75) DIO-15; T-0.31#SF EC211 DIO-07; T-0.32#SF UNE UN AMERICAN GREEN (\$75) DIO-127 CFS UD-13#SF EC212 DIO-07; T-0.32#SF UNE UN AMERICAN GREEN (\$75) DIO-07; T-0.32#SF EC212 DIO-07; T-0.32#SF EC212 DIO-07; T-0.23#SF UNE UN AMERICAN GREEN (\$75) DIO-07; T-0.23#SF EC212 DIASS RIP RAP DISSPATER PAD (RL X & WX 12	ABILIZE IT.				•	
Image: State in the second state in						
REANCE ELINE WIN. MARRICAN GREEN (375) ERSION DITCH ERSION DITCH ERS	IND		EC210			Z
ERSION DITCH ERSION DITCH ERSION DITCH NE OUTLET LUNE W. N. MERICAN GREEN (573) EDT 24 CFS; VT0 25 HB 71 20 DEEP W. 91 SIDES LUNE W. N. MERICAN GREEN (573) EC212 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC212 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC213 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC213 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC214 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS A RIP RAP DISSIPATER PAD (12L X 6W X 1870) EC223 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC223 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MITHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MITHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MUTHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION	RBANCE					
ERSION DITCH ERSION DITCH ERSION DITCH NE OUTLET LUNE W. N. MERICAN GREEN (573) EDT 24 CFS; VT0 25 HB 71 20 DEEP W. 91 SIDES LUNE W. N. MERICAN GREEN (573) EC212 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC212 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC213 D10- 0.75 : T-14.3 MSF. B-2.7 USE 0.5 FB 71 100 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) D10- 0.75 : T-0.29 MSF. B-2.7 USE 0.28 FB 71 00 DEEP W. 31 SIDES LUNE W. N. MERICAN GREEN (575) EC213 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC214 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS A RIP RAP DISSIPATER PAD (12L X 6W X 1870) EC223 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC222 CLASS B NIP RAP DISSIPATER PAD (12L X 6W X 1870) EC223 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MITHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MITHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION MUTHON MUTHON MUTHON MAR EC228 TEMPORARY HORSESHOE INLET PROTECTION		Ī				
ersion Dirch Ersion Dirch We outlet LIWAY / RIP RAP EOUTLET LIWAY / RIP RAP EC212 DIFDE WI ALMERICAN GREEN (575) EC212 DIFDE WI ALMERICAN GREEN (575) EC212 DIFDE WI ALMERICAN GREEN (575) EC213 DIFD - 127 CFS; VID= 2.37 FPS USE 0.25 FBD 1.07 DEEP W3.1 SIDES LINE WI ALMERICAN GREEN (575) EC213 DIFD - 127 CFS; VID= 2.37 FPS EC213 DIFD - 127 CFS; VID= 2.37 FPS EC213 DIFD - 127 CFS; VID= 2.37 FPS EC215 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC224 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC225 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS B RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS A RIP RAP DISSIPATER PAD (181 X 6W X 18*D) EC226 CLASS			EC211	Q10 = 5.3 CFS; V10= 2.26 FPS		
ECUTION HOUT ECTION HOUT ET PROTECTION ECTIO	ERSION DITCH			USE 0.5' FBD' 1.25' DEEP W/ 3:1 SIDES		
ECUTION HOUT ECTION HOUT ET PROTECTION ECTIO		ľ		PERMANENT DIVERSION DITCH #7	651	VD WILMINC COUNTY - NORTH CAROLII
ECUTION HOUT ECTION HOUT ET PROTECTION ECTIO	NE OUTLET ILLWAY / RIP RAP		EC212	Q10 = 2.4 CFS; V10= 5.18 FPS		1 T Y S Y
ECUTION HOUT ECTION HOUT ET PROTECTION ECTIO				USE 0.5' FBD' 1.00' DEEP W/ 3:1 SIDES		
ECUTION HOUT ECTION HOUT ET PROTECTION ECTIO		ŀ		PERMANENT DIVERSION DITCH #8	Z	
EC PROTECTION EC216 CLASS B RIP RAP DISSIPATER PAD (1612 X 6W X 18°D) EC216 CLASS A RIP RAP DISSIPATER PAD (161 X 6W X 18°D) EC217 CLASS A RIP RAP DISSIPATER PAD (161 X 4 5W X 12°D) CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE EC221 ILC PHADE (L. UTILITY WORK ON THE UTILITY PLAN). EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILLM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC225 CLASS A RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC226 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1°=40' 40' 80' B' B' B' B' B' B' B' B' B' B	ENTRANCE		EC213	Q10 = 7.2 CFS; V10= 2.37 FPS		
EC PROTECTION EC216 CLASS B RIP RAP DISSIPATER PAD (1612 X 6W X 18°D) EC216 CLASS A RIP RAP DISSIPATER PAD (161 X 6W X 18°D) EC217 CLASS A RIP RAP DISSIPATER PAD (161 X 4 5W X 12°D) CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE EC221 ILC PHADE (L. UTILITY WORK ON THE UTILITY PLAN). EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILLM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC225 CLASS A RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC226 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1°=40' 40' 80' B' B' B' B' B' B' B' B' B' B	ET PROTECTION			USE 0.25' FBD' 1.00' DEEP W/ 3:1 SIDES		
EC PROTECTION EC216 CLASS B RIP RAP DISSIPATER PAD (1612 X 6W X 18°D) EC216 CLASS A RIP RAP DISSIPATER PAD (161 X 6W X 18°D) EC217 CLASS A RIP RAP DISSIPATER PAD (161 X 4 5W X 12°D) CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE EC221 ILC PHADE (L. UTILITY WORK ON THE UTILITY PLAN). EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILLM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC225 CLASS A RIP RAP DISSIPATER PAD (181 X 9W X 18°D) EC226 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1°=40' 40' 80' B' B' B' B' B' B' B' B' B' B	HOUT		EC214			
EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (18'L X 9'W X 18"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1"=40' 30'		-				₩ § ₩
EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (18'L X 9'W X 18"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1"=40' 30'		ŀ		CLASS A RIP RAP DISSIPATER PAD (6'L X 4.5'W X 12"D)		
EC222 CIRCLE K FUNDED CONSTRUCTION WORK EC223 ILM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (18'L X 9'W X 18"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 CLASS A RIP RAP DISSIPATER PAD (18'L X 9'W X 12"D) EC225 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1"=40' 30'			EC221	SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON		
EC223 ILM FUNDED CONSTRUCTION WORK EC224 CLASS B RIP RAP DISSIPATER PAD (18'L X 9'W X 18'D) EC225 CLASS A RIP RAP DISSIPATER PAD (8'L X 6'W X 12'D) EC226 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1"=40' 40' 40' 80'		F	EC222		N S	
EC225 CLASS A RIP RAP DISSIPATER PAD (8'L X 6'W X 12"D) EC226 TEMPORARY HORSESHOE INLET PROTECTION SCALE 1"=40' 40' 80'		ŀ	EC223	ILM FUNDED CONSTRUCTION WORK		
SCALE 1"=40' 40' 80' SCALE 1"=40' 37630.054			EC225	CLASS A RIP RAP DISSIPATER PAD (8'L X 6'W X 12"D)		
SCALE 1"=40' 40' 80' SCALE 1"=40' 37630.054		l	EC226		O	
SCALE 1"=40' 40' 80' JOB NO. 37630.054)					<u> </u>
SCALE 1"=40' 40' 80' JOB NO. 37630.054						$ \mathbf{Y} $
SCALE 1"=40' 40' 80' JOB NO. 37630.054	m					ш
SCALE 1"=40' 40' 80' JOB NO. 37630.054	AD 8					_
40' 80' JOB NO. 37630.054	Z					
40' 80' JOB NO. 37630.054	SCALE 1"=40'					
JOB NO. 37630.054	40' 80'					
						JOB NO.



SEAL SEAL DECOMPOSE SEAL SEAL SEAL SEAL SEAL SEAL SEAL SE	IRON BANK	A CONTRACTOR OF A CONTRACTOR O		J		
THIS DRAWING PREPARED AT THE RALEIGH OFFICE 5410 Trinity Road, Suite 102 Raleigh, NC 27607 TEL 919.866.4951 FAX 919.833.8124 www.timmons.com	REVISION DESCRIPTION	REVISION PER CFPUA REVIEW	NEW HANOVER COUNTY STORMWATER SUBMITTAL			
YOUR VISION ACHIEVED THROUGH OURS.	DATE	6 09/11/2020	D9/21/2020	E 2020)	
INORTH CAROLINA LICENSE NO. C-1652						These plans and associated documents are the exclusive property of TIMMONS GROUP and may not be reproduced in whole or in part and shall not be used for any purpose whatsoever, inclusive, but not immed to construction bidding and/or construction staking without the express written consent of TIMMONS GROUP

GROUND STABILIZATION HATCHES								
НАТСН	SITE AREA DESCRIPTION							
	SLOPES STEEPER THAN 3: REFER TO SECTION E OF N GROUND STABILIZATION AN MATERIALS HANDLING							
	SLOPES 3:1 TO 4:1; REFER SECTION E OF NCG01 GRO STABILIZATION AND MATER HANDLING							



SAN 24		SEAL SEAL CZ255 VGININ	ROUTEN 111111111111111111111111111111111111
		THIS DRAWING PREPARED AT THE RALEIGH OFFICE 5410 Trinity Road, Suite 102 Raleigh, NC 27607 TEL 919.866.4951 FAX 919.833.8124 www.timmons.com	REVISION DESCRIPTION REVISION PER CFPUA REVIEW NEW HANOVER COUNTY STORMWATER SUBMITTAL
BO		YOUR VISION ACHIEVED THROUGH OURS.	DATE 09/11/2020 09/21/2020 NEW HAN
		YOUR V	09/02/2020 DRAWN BY A. MAY DESIGNED BY B. DOWNS CHECKED BY R. BAKER SCALE AS SHOWN
~~~~	GROUND STABILIZATION HATCHES         HATCH       SITE AREA DESCRIPTION         WXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX		TON - NC.115
	REFER TO SECTION E OF NCG01 GROUND STABILIZATION AND MATERIALS HANDLING SLOPES 3:1 TO 4:1; REFER TO SECTION E OF NCG01 GROUND STABILIZATION AND MATERIALS HANDLING REFER TO NPDES STABILIZATION NOTES AND DETAILS FOR ADDITIONAL REQUIREMENTS AND INFORMATION.	LICENSE NO. C-1652	VD WIL COUNTY - NORT PLAN In part and shall not be use
	EROSION CONTROL LEGEND         LOD       LIMITS OF DISTURBANCE         SF       SF         SF       SF         SF       SF         POROUS BAFFLE		NTI AIRPORT BL WILMINGTON - NEW HANOVER NPDES
80'	PERMANENT DIVERSION DITCH   TEMPORARY DIVERSION DITCH   SILT FENCE STONE OUTLET   EMERGENCY SPILLWAY / RIP RAP   APRON   CHECK DAM   CONSTRUCTION ENTRANCE   TEMPORARY INLET PROTECTION   CONCRETE WASHOUT		CIRCLE K - NTI AIRP WILMINGTON - WILMINGTON - MILMINGTON

37630.054

SHEET NO.

C4.5

40'

HORSESHOE INLET PROTECTION SKIMMER

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT         Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.         SECTION E: GROUND STABILIZATION         Required Ground Stabilization Timeframes         Stabilize within this many calendar	<ol> <li>EQUIPMENT AND VEHICLE MAINTENANCE         <ol> <li>Maintain vehicles and equipment to prevent discharge of fluids.</li> <li>Provide drip pans under any stored equipment.</li> <li>Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.</li> <li>Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).</li> <li>Remove leaking vehicles and construction equipment from service until the problem has been corrected.</li> <li>Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.</li> </ol> </li> </ol>	DINSITE CONCRETE WASHDUT STRUCTURE VITH LINER	SEAL D22530 W. BANKING OF/21/2020
Image: Section of Construction of Construction activities, and perimeter slopes       7       None         (a) Perimeter dikes, swales, ditches, and perimeter slopes       7       None         (b) High Quality Water (HQW) Zones       7       None         (c) Slopes steeper than 3:1       7       None         (d) Slopes 3:1 to 4:1       14       -7 days for slopes greater than 50' in length and with slopes steeper than 4:1.         (d) Slopes 3:1 to 4:1       14       -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones         (e) Areas with slopes flatter than 4:1       14       -7 days for Falls Lake Watershed         Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be construction activities, any areas with temporary graund stabilization is achieved.         FROUND STABILIZATION SPECIFICATION         Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:         Permanent Stabilization         • Temporary grass seed covered with straw or other mulches and tackifiers         • Hydroseeding       • Permanent stabilization         • Rolled erosion control products with or without temporary grass seed       • Permanent stabilization     <	<ul> <li>IITTER, BUILDING MATERIAL AND LAND CLEARING WASTE         <ol> <li>Never bury or burn waste. Place litter and debris in approved waste containers.</li> <li>Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.</li> <li>Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.</li> <li>Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.</li> <li>Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.</li> <li>Anchor all lightweight items in waste containers during times of high winds.</li> <li>Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.</li> <li>Dispose waste off-site at an approved disposal facility.</li> <li>On business days, clean up and dispose of waste in designated waste containers.</li> </ol></li></ul> <li>PAINT AND OTHER LIQUID WASTE         <ul> <li>Do not dump paint and other liquid waste into storm drain, streams or wetlands.</li> <li>Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.</li> <li>Contain liquid wastes in a controlled area.</li> <li>Contain ment must be labeled, sized and placed appropriately for the needs of site.</li> <li>Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.</li> </ul> </li> <li>PORTABLE TOILETS         <ul> <li>Install portable toilets on level ground, at least 50 feet away from storm</li></ul></li>	<ul> <li>CONCRETE WASHOUTS <ol> <li>Do not discharge concrete or cement slurry from the site.</li> <li>Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.</li> <li>Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.</li> <li>Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.</li> <li>Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.</li> <li>Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.</li> <li>Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.</li> <li>Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.</li> <li>At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if appli</li></ol></li></ul>	Intervention       This Drawing prepared at THE         Ralergeh OFFICE       S410 Trinity Road, Suite 102   Raleigh, NC 27607         TeL 919.866.4951 FAX 919.833.8124 www.timmons.com         TeL 919.866.4951 FAX 919.833.8124 www.timmons.com         ReVISION DESCRIPTION         ReVISION PER CFPUA REVIEW         New HANOVER COUNTY STORMWATER SUBMITTAL
<ul> <li>Uniform and evenly distributed ground cover sufficient to restrain erosion</li> <li>Structural methods such as concrete, asphalt or retaining walls</li> <li>Rolled erosion control products with grass seed</li> </ul> <b>POLYACRYLAMIDES (PAMS) AND FLOCCULANTS</b> <ol> <li>Select flocculants that are appropriate for the soils being exposed during construction, selecting from the <i>NC DWR List of Approved PAMS/Flocculants</i>.</li> <li>Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.</li> <li>Apply flocculants at the concentrations specified in the <i>NC DWR List of Approved PAMS/Flocculants</i> and in accordance with the manufacturer's instructions. Provide ponding area for containment of treated Stormwater before discharging offsite. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.</li></ol>	<ul> <li>EARTHEN STOCKPILE MANAGEMENT         <ol> <li>Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.</li> <li>Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.</li> <li>Provide stable stone access point when feasible.</li> <li>Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.</li> </ol> </li> <li>STABILIZATION AND MATERIALS F</li> </ul>	<ol> <li>Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.</li> <li>Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.</li> <li>Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.</li> <li>Do not stockpile these materials onsite.</li> <li>MAZARDOUS AND TOXIC WASTE         <ul> <li>Create designated hazardous waste collection areas on-site.</li> <li>Place hazardous waste containers under cover or in secondary containment.</li> <li>Do not store hazardous chemicals, drums or bagged materials directly on the ground.</li> </ul> </li> <li>EFFECTIVE: 04/01/19</li> </ol>	DATE 09/02/2020 DRAWN BY A. MAY DESIGNED BY B. DOWNS CHECKED BY R. BAKER
PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING	PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING	PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING	SCALE AS SHOWN
SECTION A: SELF-INSPECTION         Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.         Inspect       If requency (during normal business hours).       Inspection records must include:         (1) Rain gauge maintained in gord working order       Daily rainfall amounts.       If no daily rainfall amounts.       If no daily rainfall amounts.         (2) E&SC       At least once per 7 calendar days and within 24 hours 2 1.0 inch in 24 hours       At least once per 7 calendar days and within 24 hours of a rain event 2 1.0 inch in 24 hours       I. Identification of the inspection, 4. Indication of the inspection, 4. Indication of the inspection, 4. Indication of the inspection, 4. Secription, evidence, and date of corrective actions taken.         (3) Stormwater discharge outfalls (SDCs)       At least once per 7 calendar days and within 24 hours of a rain event 2 1.0 inch in 24 hours       1. Identification of the inspection, 4. Indication of the inspection, 4. Name of the person performing the inspection, 4. Name of the person performing the inspection, 4. Sume of the person performing the inspection, 4. Sume of the person performing the inspection, 4. Sumere of the person performing the inspection, 4. Sume of	SECTION B: RECORDKEEPING         1. E&SC Plan Documentation         The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.         Item to Document       Documentation Requirements         (a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.       Initial and date each E&SC measure on a copy of the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures or if the E&SC measures are modified after initial installation.         (b) A phase of grading has been completed.       Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.         (c) Ground cover is located and installed in accordance with the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.         (d) The maintenance and repair       Complete, date and sign an inspection report.	<ul> <li>SECTION C: REPORTING</li> <li>1. Occurrences that Must be Reported Permittees shall report the following occurrences: <ul> <li>(a) Visible sediment deposition in a stream or wetland.</li> </ul> </li> <li>(b) Oil spills if: <ul> <li>They are 25 gallons or more,</li> <li>They are less than 25 gallons but cannot be cleaned up within 24 hours,</li> <li>They cause sheen on surface waters (regardless of volume), or</li> <li>They are within 100 feet of surface waters (regardless of volume).</li> </ul> </li> <li>(c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.</li> <li>(d) Anticipated bypasses and unanticipated bypasses.</li> <li>(e) Noncompliance with the conditions of this permit that may endanger health or the environment.</li> </ul>	-1652 -1652 110GTON - NC.115 CAROLINA LS
DRAW DOWN OF SEDIMENT BA Sediment basins and traps that receive runoff from drainage areas of one acre or more shall us for maintenance or close out unless this is infeasible. The circumstances in which it is not feas Non-surface withdrawals from sediment basins shall be allowed only when all of the following	requirements for all E&SC measures have been performed.         (e) Corrective actions have been taken to E&SC measures.       Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.         2. Additional Documentation to be Kept on Site In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:         (a) This General Permit as well as the Certificate of Coverage, after it is received.         (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.         3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]         SECTION G, ITEM (4) ASINS FOR MAINTENANCE OR CLOSE OUT         se outlet structures that withdraw water from the surface when these devices need to be drawn dow sible to withdraw water from the surface shall be rare (for example, times with extended cold weather criteria have been met:	(c) Anticipated       • A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.         (d) Unanticipated bypasses [40 CFR       • Within 24 hours, an oral or electronic notification.         (d) Unanticipated bypasses [40 CFR       • Within 2 calendar days, a report that includes an evaluation of the quality and effect of the bypass.         (e) Noncompliance err).       • Within 2 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)[6].	<ul> <li>A O D D S B G B</li> <li>A O D D S D S D B B C B</li> <li>A D S NOTES AND DETAIL</li> </ul>
(4) Perimeter of site       At least once per 7 calendar days and within 24       If visible sedimentation is found outside site limits, then a record of the following shall be made: Actions taken to clean up or stabilize the sediment that has left the site limits, event ≥ 1.0 inch in 24 hours         (5) Streams or wetlands onsite or offsite       At least once per 7 calendar days and within 24       If wisible sedimentation as to the actions taken to control future releases.         (5) Streams or wetlands onsite or offsite       At least once per 7 calendar days and within 24       If wisible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: . Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.         (6) Ground stabilization measures       After each phase of grading       1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover).         NOTE: The rain inspection resets the required 7 calendar day inspection requirement.         PART III, S DRAW DOWN OF SEDIMENT B/ Sediment basins and traps that receive runoff from drainage areas of one acre or more shall uf for maintenance or close out unless this is infeasible. The circumstances in which it is not feas Non-surface withdrawals from sediment basins shall be allowed only when all of the following (a) The E&SC plan authority has been provided with documentation of the non-surface wis shall not commence until the E&SC plan authority	have been performed.         Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.           2. Additional Documentation to be Kept on Site         In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:           (a)         This General Permit as well as the Certificate of Coverage, after it is received.           (b)         Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.           3. Documentation to be Retained for Three Years         All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]           SECTION G, ITEM (4)         ASINS FOR MAINTENANCE OR CLOSE OUT           se outlet structures that withdraw water from the surface when these devices need to be drawn dow sible to withdraw water from the surface shall be rare (for example, times with extended cold weather criteria have been met:           with Part III, Section C, Item (2)(c) and (d) of this permit, om stormwater that is removed from the sediment basin. Examples of appropriate controls	After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368. <b>Occurrence Reporting Timeframes (After Discovery) and Other Requirements</b> (a) Visible sediment <b>Within 24 hours</b> , an oral or electronic notification.             (a) Visible sediment         deposition in a         stream or wetland <b>Within 24 hours</b> , an oral or electronic notification.             (b) Oil spills and         related causes, the permittee may be requirement for a written report on a         case-by-case basis.           (b) Oil spills and         related causes, an oral or electronic notification.         The report shall include information about the date, time, nature, volume and         location of the spill or release.             (b) Oil spills and         related Core of the bypass. <b>A report at least ten days before the date of the bypass</b> , if possible.         The report shall include an evaluation of the anticipated quality and         effect of the bypass.             (d) Unanticipated         bypasses [40 CFR         122.41(m)(3)]           Within 24 hours, an real or electronic notification.         the quality and effect of the bypass.             (a) Concompliance         within 24 hours, an oral or electronic notification.         for the spasses	O D D D D D D D D D D D D D D D D D D D
[4] Perimeter of site       At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours       If wishle sedimentation is found outside site limits, the stel limits,         [5] Streams or wetsands onsite or offsite where ≥ 1.0 inch in 24 hours       A nexplanation as to the actions taken to control future releases.         [6] Streams or wetsands onsite or offsite accessible       A teast once per 7 calendar days and within 24 hours of a rain accessible       If the stream or wetland has increased visible sedimentation or a tativath has visible increased turbidity from the construction activity, then a record of the following shall be made:         [6] Ground stabilization measures       At least once per 7 calendar days and within 24 hours of a rain accessible       If the stream or wetland has increased visible sedimentation or a tativath has of parking (installation of perimeter E&SC dift required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.         [6] Ground stabilization measures       After each phase of grading facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover).         2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.         NOTE: The rain inspection resets the required 7 calendar day inspection requirement.         Sediment basins and traps that receive runoff from drainage areas of one acre or more shall u for maintenance or close out unless this is infeasible. The circumstances in which it is not feas Non-surface withdrawal has been reported a	have been performed.         Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.           2. Additional Documentation to be Kept on Site         In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:           (a)         This General Permit as well as the Certificate of Coverage, after it is received.           (b)         Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.           3. Documentation to be Retained for Three Years         All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]           SECTION G, ITEM (4)         ASINS FOR MAINTENANCE OR CLOSE OUT           se outlet structures that withdraw water from the surface when these devices need to be drawn dow sible to withdraw water from the surface shall be rare (for example, times with extended cold weather criteria have been met:           with Part III, Section C, Item (2)(c) and (d) of this permit, om stormwater that is removed from the sediment basin. Examples of appropriate controls	After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the orter requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.           Cocurrence         Reporting Timeframes (After Discovery) and Other Requirements           (a) Visible sediment deposition in a stream or wetland         • Within 24 hours, an oral or electronic notification.           • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis.           • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.           (b) Oli spills and release of hazardous         • Within 24 hours, an oral or electronic notification shall include information about the date, time, nature, volume and location of the spill or release.           (c) Anticipated bypasses (40 CFR 124.41(m)(3)         • Within 24 hours, an oral or electronic notification.           (b) Unanticipated bypasses (40 CFR 201.41(m) and effect of the bypass.         • Within 24 hours, an oral or electronic notification.           (c) Anticipated bypasses (40 CFR 124.41(m)(3)         • Within 24 hours, an oral or electronic notification.           (c) Rin sperithi	O D D D D D D D D D D D D D D D D D D D

		<b>1</b>
<ul> <li>ANCE WITH construction Handling ely). The y the this sheet jurisdiction.</li> <li>Beguir And VEHICLE MAINTENANCE         <ol> <li>Maintain vehicles and equipment to prevent discharge of fluids.</li> <li>Provide drip pans under any stored equipment.</li> <li>Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.</li> <li>Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).</li> <li>Remove leaking vehicles and construction equipment from service until the problem has been corrected.</li> <li>Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.</li> </ol> </li> </ul>	DNSITE CONCRETE VASHDUT STRUCTURE VITH LINE UNIT TORE UNIT TORE	SEAL D22530 W BANNIN 09/21/2020
<ul> <li>I. Never bury or burn waste. Place litter and debris in approved waste containers.</li> <li>Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.</li> <li>Locate waste containers at least 50 feet away from storm drain inlets and surface water sunless no other alternatives are reasonably available.</li> <li>Locate waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.</li> <li>Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.</li> <li>Cover waste containers and the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.</li> <li>Cover waste containers and the end of each workday and before storm events or provide secondary containmers.</li> <li>Denoted limptweight items in waste containers during times of high winds.</li> <li>Empty waste containers and dispose of waste in designated waste containers.</li> <li>Mort AND OTHER LQUID WASTE</li> <li>Do not dump paint and other liquid waste into storm drain inlets and surface waters unless no other alternatives are reasonably available.</li> <li>Contain liquid wastes in a controled area.</li> <li>Contain liquid waste in a controled area.</li> <li>Contain liquid waste in a controled area.</li> <li>Contain liquid waste in a controled area.</li> <li>Provide staking or anchoring of portable toilets during periods of high winds or in high for traffic areas.</li> <li>Monitor portable toilets on level ground, at least 50 feet away from storm drains, streams or wetland.</li> <li>Locate paint washouts at least 50 feet away from storm drains, streams or wetland.</li> <li>Locate paint washouts all least for least sof get away from storm drains, streams o</li></ul>	<ul> <li>CONCRETE WASHOUTS         <ol> <li>Do not discharge concrete or cement slurry from the site.</li> <li>Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.</li> <li>Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.</li> <li>Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.</li> <li>Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.</li> <li>Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout twich could receive spills or overflow.</li> <li>Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.</li> </ol></li></ul> <li>Install at least one sign directing concrete trucks to the washout within the project limit. Post signage on the washout tiself to identify this location.</li> <li>Remove leavings from the washout tiself to identify this location.</li> <li>At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicabl</li>	YOUR VISION ACHIEVED THROUGH OURS.       THIS DRAWING PREPARED AT THE         YOUR VISION ACHIEVED THROUGH OURS.       RALEIGH OFFICE         YOUR VISION ACHIEVED THROUGH OURS.       5410 Trinity Road, Suite 102   Raleigh, NC 27607         TEL 919.866.4951 FAX 919.833.8124 www.timmons.com       TEL 919.866.4951 FAX 919.833.8124 www.timmons.com         AMWAR       DATE       REVISION DESCRIPTION         ALW WAR       09/21/2020       NEW HANOVER COUNTY STORMWATER SUBMITTAL
ND STABILIZATION AND MATERIALS HA	ANDLING EFFECTIVE: 04/01/19	CHECKED BY R. BAKER
PART III         SELF-INSPECTION, RECORDREPING AND REPORTING         Standard of the approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.         Intend or base of standard or the approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection stall times during normal business hours.         Intend or base of standard or base of standard or the approved E&SC plan.       Intend or othe approved E&SC plan the approved E&SC plan. This documentation is required upon the hintial installation of the ESC measures or if the E&SC measures are modified after initial installation.         (a) Exot E&SC measures are modified after initial installation.       Initial and date a copy of the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures are modified after initial installation.         (b) A phase of grading has been completed.       Initial and date a copy of the approved E&SC plan.         (c) Ground cover is located and installed in accordance with the approved E&SC plan modules complete, date and sign an inspection report to indicate complete with approved ground cover specifications.         (d) The maintenance and repair required interaction to the E&SC measures in a dial and addate a copy of the approved E&SC plan.         (a) The Ground cover is located and installed in a condicate complete ond the cof E	PART III           SECTION C: REPORTING           SECTION C: REPORTING           1. Occurrences that Must be Reported Permittees shall report the following occurrences: <ul> <li>(a) Visible sediment deposition in a stream or wetland.</li> <li>(b) Oil spills if:                 <ul> <li>They are 25 gallons or more,</li> <li>They are less than 25 gallons but cannot be cleaned up within 24 hours,</li> <li>They cause sheen on surface waters (regardless of volume), or</li> <li>They cause sheen on surface waters (regardless of volume),</li> <li>Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.</li></ul></li></ul>	Report North Contraction of the series of th
PART II, SECTION G, ITEM (4) SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down in it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). the following criteria have been met: on-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal is, accordance with Part III, Section C, Item (2)(c) and (d) of this permit, pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include filtration systems,	(d) Unanticipated bypasses [40 CFR       • Within 24 hours, an oral or electronic notification.         (e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41{(l){7}]       • Within 24 hours, an oral or electronic notification.         (e) Noncompliance with the conditions of this permit that may endanger health or the environment[40       • Within 2 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l){6}.         • Division staff may waive the requirement for a written report on a case-by-case basis.	NOR NNOR
ed to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, o are provided at the discharge points of all dewatering devices, and orm (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.	PORTING EFFECTIVE: 04/01/19	
-INSPECTION, RECORDKEEPING AND REP	UNITING EFFECTIVE: 04/01/19	

## PRELIMINARY - NOT RELEASED FOR CONSTRUCTION

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




37630.054

JOB NO.

SHEET NO.

C4.6



		UTILITY PLAN KEYNOTES		
	NUMBER	DESCRIPTIONTELEPHONE SERVICE POINT OF ENTRY TO BUILDING; REFER TO ARCHITECTURAL PLANS BY OTHERS. COORDINATE WITH LOCAL PROVIDER AND CIRCLE K CONSTRUCTION MANAGER FOR ACCOUNT SETUP. PROVIDE A 2" CONDUIT FOR TELEPHONE FROM BUILDING TO POINT OF CONNECTION. PROVIDE A 3"	HID OF ES	
<u>nen</u> T	CU01	CONDUIT FOR CABLE/INTERNET FROM BUILDING TO PEDESTAL. CONDUIT RUNS BURIED A MINIMUM OF 24" BELOW GRADE AND HAVE A PULL STRING INSTALLED. CONDUIT RUNS MUST NOT EXCEED A TOTAL OF 180° DEGREES OF BEND WITHOUT A PULL BOX. STANDARD 90° BEND IS 6' BENDS WITH 3' RADIUS.	WGN W	BAKKIIII 09/21/2020
	CU02	TRANSFORMER PAD LOCATION. COORDINATE WITH LOCAL PROVIDER. LOCAL PROVIDER CAN SUPERSEDE THE PROPOSED TRANSFORMER PAD LOCATION. PROVIDE TWO (2) 6" CONDUITS BETWEEN POINT OF CONNECTION AND TRANSFORMER. 24" MINIMUM BURY DEPTH WITH 18" OF VERTICAL SEPARATION AT WATER AND SEWER CROSSINGS.	AT THE eigh, NC 27607 www.timmons.com	AL
	CU03 CU04	ELECTRIC SERVICE POINT OF ENTRY TO BUILDING; REFER TO MEP PLANS BY OTHERS. COORDINATE WITH LOCAL PROVIDER. WATER LINE POINT OF CONNECTION.	AT THE eigh, NC www.tim	V SUBMITTAI
GAS LINE DRAWN FROM G	CU05	2" TYPE K COPPER DOMESTIC WATER SERVICE; CONFIRM SIZE WITH MEP PLANS BY OTHERS.	DRAWING PREPARED AT THE <b>RALEIGH OFFICE</b> Road, Suite 102   Raleigh, NC 1 FAX 919.833.8124 www.ti	
— UGP	CU06 CU07	1.5" DOMESTIC WATER METER1.5" DOMESTIC RPZ BACKFLOW PREVENTER (PER LOCALREQUIREMENTS) DOWNSTREAM OF THE WATER METER.		DESCRIPTION R CFPUA REVIE
UGT	CU08	PROVIDE POWER TO HOT BOX. REFER TO DETAIL CK-240. WATER LINE POINT OF ENTRY TO BUILDING; REFER TO MEP	THIS DRAWING <b>RALEIG</b> inity Road, Suite 6.4951 FAX 919	
	CU09	PLANS BY OTHERS. 2" x 3/4" TEE, BALL VALVE, AND 3/4" TYPE K COPPER DOMESTIC	THIS D 10 Trinity Rc	REVISION D VISION PER ER COUNTY (
	CU10	WATER SERVICE FOR AIR AND WATER MACHINE. WATER LINE POINT OF ENTRY TO AIR AND WATER MACHINE.	5410 T 919.86	REVI EVISI
	CU11 CU12	5/8" IRRIGATION METER 3/4" RPZ IRRIGATION BACKFLOW PREVENTER (PER LOCAL REQUIREMENTS) DOWNSTREAM OF THE IRRIGATION METER.	TEL	ANOV
	CU13	PROVIDE POWER TO HOT BOX. REFER TO DETAIL CK-240. 1" IRRIGATION WATER LINE. REFER TO IRRIGATION PLANS BY OTHERS AND DETAILS CK-230 AND CK-235. PROVIDE AS-BUILT TO CIRCLE K CONSTRUCTION MANAGER.	H OURS.	REV NEW HANOVE
	CU14	APPROXIMATE IRRIGATION CONTROLLER LOCATION. OWNER'S REPRESENTATIVE SHALL PINPOINT EXACT LOCATION ON-SITE. IRRIGATION CONTRACTOR SHALL HARDWIRE POWER TO CONTROLLER. REFER TO IRRIGATION PLANS BY OTHERS.	YOUR VISION ACHIEVED THROUGH OURS.	
	CU15 CU16	SANITARY SEWER POINT OF CONNECTION. 6" PVC SANITARY SEWER SERVICE @ 1/8" PER LF MIN. SLOPE, 4'	HIEVED	DATE /11/202 /21/202
	CU17	MIN. COVER (TYP.). SANITARY SEWER CLEANOUT. TRAFFIC RATED IF WITHIN	UN ACH	DATE 09/11/2020 09/21/2020
	CU18	PAVEMENT (TYP.). REFER TO DETAIL CK-205. SANITARY SEWER TWO-WAY CLEANOUT; REFER TO PLUMBING DETAIL ON P1.3 AND CK-205.	VISIC	DATE
	CU19	SANITARY SEWER WYE CONNECTION. GREASE TRAP; REFER TO MEP PLANS BY OTHERS FOR SIZING,	YOUR	09/02/2020 DRAWN BY
	CU20	VENTING, AND DETAILS. SANITARY SEWER POINT OF ENTRY TO BUILDING; REFER TO MEP		A. MAY
	CU21 CU22	PLANS BY OTHERS. GREASE SERVICE POINT OF ENTRY TO BUILDING; REFER TO MEP		DESIGNED BY
	CU23	PLANS BY OTHERS. CONTRACTOR TO VERIFY EXISTING UTILITY LOCATIONS PRIOR TO START OF CONSTRUCTION. IMMEDIATELY NOTIFY CLIENT AND ENGINEER IF DISCREPANCIES OR CONFLICTS ARE FOUND.		B. DOWNS CHECKED BY R. BAKER
	CU25	PROVIDE POWER TO AIR AND WATER MACHINE. CIRCLE K VENDOR TO PROVIDE AIR AND WATER MACHINE. PROVIDE POWER TO MID SIGN; WIRED BY BUILDING ELECTRICAL		SCALE
	CU27	CONTRACTOR. VERIFY EXACT LOCATION AND DESIGN BEFORE ROUGH-IN. PERMITTED BY OTHERS.	•	AS SHOWN
8" PVCSAN	CU28	LIGHT POLE BASE; REFER TO DETAIL CK-190. REFER TO LIGHTING, ELECTRICAL, AND STRUCTURAL PLANS BY OTHERS (TYP.). PROVIDE 2" CONDUIT FOR FUTURE ELECTRIC CHARGING	•	[15
	CU39	STATION FROM BUILDING. STUB AND CAP 8" ABOVE FINISHED GRADE. CONDUIT RUNS BURIED A MINIMUM OF 24" BELOW GRADE AND HAVE A PULL STRING INSTALLED. CONDUIT RUNS MUST NOT EXCEED A TOTAL OF 180° DEGREES OF BEND WITHOUT A PULL BOX. STANDARD 90° BEND IS 6' BENDS WITH 3' RADIUS.		- NC.1
1 DUT 17.24	U01 U02	EXISTING FIRE HYDRANT EXISTING WATER LINE; CONFIRM PRIOR TO CONSTRUCTION EXISTING SANITARY SEWER MANHOLE (TYP.)		z
	U06 U07	EXISTING SANITARY SEWER MANHOLE (TTP.) EXISTING SANITARY SEWER MAIN (TYP.) EXISTING UTILITY POLE (TYP.)		0
	U09 U10	EXISTING OTILITY FOLE (TTP.) EXISTING OVERHEAD UTILITY LINE (TYP.) EXISTING FORCE MAIN; CONFIRM PRIOR TO CONSTRUCTION		U U U
	U13 U18	EXISTING GAS MAIN TO REMAIN	1652	<b>AING</b> CAROLINA
1) LOCATE ALL	U19 U20	EXISTING TELEPHONE LINES TO REMAIN EXISTING UNDERGROUND POWER LINE TO REMAIN		Σ ^T
SHOULD BE VERIFIED IN THE	U31 U38	FIRE HYDRANT ASSEMBLY (TYP.) 6" GATE VALVE (TYP.)		VILMIN( - NORTH CAROLI
NEER OTED.	U39 U54	8" GATE VALVE (TYP.) 5' (INSIDE DIAMETER) MANHOLE		AN NA
CATION OF ALL LECTRIC AND GAS	U58	CONNECT TO EXISTING SANITARY SEWER MANHOLE. CORE DRILL AND INSTALL FLEXIBLE RUBBER BOOT. (CONTRACTOR TO FIELD VERIFY LOCATION AND ELEVATION)		
R THE CITY PRIOR /IDE CONDUITS AS	U72	COORDINATE WITH WATER DEPARTMENT TO ENSURE THAT SERVICE IS NOT INTERRUPTED AT ANY TIME.		
ATIC AND MAY NOT Y THE DESIGN	U73 U74	30' WIDE CFPUA SANITARY SEWER EASEMENT. 20' WIDE CFPUA WATER EASEMENT. CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE		ORT BL NEW HANOVER UTILITY
CIES ARE NOTED.	U75	SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).	<b>N</b> IIO	LT. LT.
E IN E OF NORTH	U76 U77	CIRCLE K FUNDED CONSTRUCTION WORK	CAR	
ONZE STRAPS	U79 U80	PROPOSED 2" SADDLE CONNECTION PROPOSED 8" x 8" x 6" TEE		RP(
DY. ER METERS.	U81 U82	PROPOSED 8" x 12" TS&V PROPOSED CORPORATION STOP		
D TO NEW	U82 U83	6" FIRE HYDRANT RPZ BACKFLOW PREVENTER (PER LOCAL REQUIREMENTS). PROVIDE POWER TO HOT BOX. REFER TO	NORT	
E, ASPHALT, DING TO NEW ATIONS.	U84	DETAIL CK-240. PROPOSED INSIDE DROP. REFER TO DETAIL.		Z
CATIONS. DRMATION IS TAKEN ED 11/20/2019. ROM OTHER			Σ	ч У

37630.054


K

 $\bigcirc$ 

JOB NO.

SHEET NO.

C5.0



ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

			UTILITY PLAN KEYNOTES		Palla.	
	SAN	NUMBER	DESCRIPTION TELEPHONE SERVICE POINT OF ENTRY TO BUILDING; REFER TO ARCHITECTURAL PLANS BY OTHERS. COORDINATE WITH LOCAL PROVIDER AND CIRCLE K CONSTRUCTION MANAGER FOR ACCOUNT SETUP. PROVIDE A 2" CONDUIT FOR TELEPHONE	SEAL		-
		CU01	FROM BUILDING TO POINT OF CONNECTION. PROVIDE A 3" CONDUIT FOR CABLE/INTERNET FROM BUILDING TO PEDESTAL. CONDUIT RUNS BURIED A MINIMUM OF 24" BELOW GRADE AND HAVE A PULL STRING INSTALLED. CONDUIT RUNS MUST NOT EXCEED A TOTAL OF 180° DEGREES OF BEND WITHOUT A PULL BOX. STANDARD 90° BEND IS 6' BENDS WITH 3' RADIUS.	E CHARLEN	9/21/202	
	- SAN-	CU02	TRANSFORMER PAD LOCATION. COORDINATE WITH LOCAL PROVIDER. LOCAL PROVIDER CAN SUPERSEDE THE PROPOSED TRANSFORMER PAD LOCATION. PROVIDE TWO (2) 6" CONDUITS BETWEEN POINT OF CONNECTION AND TRANSFORMER. 24" MINIMUM BURY DEPTH WITH 18" OF VERTICAL SEPARATION AT WATER AND SEWER CROSSINGS.	AT THE eigh, NC 27607 www.timmons.com	TAL	
		CU03	ELECTRIC SERVICE POINT OF ENTRY TO BUILDING; REFER TO MEP PLANS BY OTHERS. COORDINATE WITH LOCAL PROVIDER.	AT THE eigh, NC www.tin	V SUBMITTA	
	w	CU04	WATER LINE POINT OF CONNECTION. 2" TYPE K COPPER DOMESTIC WATER SERVICE; CONFIRM SIZE	· U	SUE	
		CU05 CU06	WITH MEP PLANS BY OTHERS. 1.5" DOMESTIC WATER METER	AWING PREPARED <b>RALEIGH OFFICE</b> ad, Suite 102   Ral FAX 919.833.8124	ESCRIPTION CFPUA REVIEW STORMWATER S	
/	– UGT	CU07	1.5" DOMESTIC RPZ BACKFLOW PREVENTER (PER LOCAL REQUIREMENTS) DOWNSTREAM OF THE WATER METER.	NG PF EIGH ulite 1 919.8	UA R NW	
SMH-/ I=24.52 I)=8.05 E)=7.85		CU08	PROVIDE POWER TO HOT BOX. REFER TO DETAIL CK-240. WATER LINE POINT OF ENTRY TO BUILDING; REFER TO MEP PLANS BY OTHERS. 2" x 3/4" TEE, BALL VALVE, AND 3/4" TYPE K COPPER DOMESTIC	THIS DRAWING PREPARED AT THE <b>RALEIGH OFFICE</b> 5410 Trinity Road, Suite 102   Raleigh, NC 919.866.4951 FAX 919.833.8124 www.ti		
/)=7.78		CU09	WATER SERVICE FOR AIR AND WATER MACHINE.	Trin 3 Trin 866.∠	SION	
		CU10 CU11	WATER LINE POINT OF ENTRY TO AIR AND WATER MACHINE. 5/8" IRRIGATION METER	- / -	REVIS	
D BE		CU12	3/4" RPZ IRRIGATION BACKFLOW PREVENTER (PER LOCAL REQUIREMENTS) DOWNSTREAM OF THE IRRIGATION METER. PROVIDE POWER TO HOT BOX. REFER TO DETAIL CK-240. 1" IRRIGATION WATER LINE. REFER TO IRRIGATION PLANS BY	LEL S.	REVISION D REVISION PER NEW HANOVER COUNTY 5	
	-	CU13	OTHERS AND DETAILS CK-230 AND CK-235. PROVIDE AS-BUILT TO CIRCLE K CONSTRUCTION MANAGER.	OUR	Z	
N OF AL		01144	APPROXIMATE IRRIGATION CONTROLLER LOCATION. OWNER'S REPRESENTATIVE SHALL PINPOINT EXACT LOCATION ON-SITE.	DUGH		
IC AND ( CITY PR	IOR	CU14	IRRIGATION CONTRACTOR SHALL HARDWIRE POWER TO CONTROLLER. REFER TO IRRIGATION PLANS BY OTHERS.	YOUR VISION ACHIEVED THROUGH OURS.		++-
ONDUITS	AS	CU15	SANITARY SEWER POINT OF CONNECTION. 6" PVC SANITARY SEWER SERVICE @ 1/8" PER LF MIN. SLOPE, 4'	EVED	DATE 09/11/2020 09/21/2020	
ND MAY I DESIGN		CU16	MIN. COVER (TYP.). SANITARY SEWER CLEANOUT. TRAFFIC RATED IF WITHIN	ACHI	DATE 9/11/20	
RE NOTI		CU17	PAVEMENT (TYP.). REFER TO DETAIL CK-205.	NOIS		<u></u>
NORTH		CU18	SANITARY SEWER TWO-WAY CLEANOUT; REFER TO PLUMBING DETAIL ON P1.3 AND CK-205.	R VIS	09/02/2	
		CU19	SANITARY SEWER WYE CONNECTION. GREASE TRAP; REFER TO MEP PLANS BY OTHERS FOR SIZING,	лоу	DRAWN	
STRAPS		CU20	VENTING, AND DETAILS. SANITARY SEWER POINT OF ENTRY TO BUILDING; REFER TO MEP		A. MA	١Y
TERS.		CU21	PLANS BY OTHERS. GREASE SERVICE POINT OF ENTRY TO BUILDING; REFER TO MEP		DESIGNE	D BY
E INTO		CU22	PLANS BY OTHERS. CONTRACTOR TO VERIFY EXISTING UTILITY LOCATIONS PRIOR		B. DOV	VNS
IEW		CU23	TO START OF CONSTRUCTION. IMMEDIATELY NOTIFY CLIENT AND ENGINEER IF DISCREPANCIES OR CONFLICTS ARE FOUND.		CHECKEI	) BY
PHALT,		CU25	PROVIDE POWER TO AIR AND WATER MACHINE. CIRCLE K VENDOR TO PROVIDE AIR AND WATER MACHINE.		R. BAK	(ER
D NEW S.		01107	PROVIDE POWER TO MID SIGN; WIRED BY BUILDING ELECTRICAL	$\bullet$ $\bullet$	SCAL	
ON IS TA	KEN	CU27	CONTRACTOR. VERIFY EXACT LOCATION AND DESIGN BEFORE ROUGH-IN. PERMITTED BY OTHERS.		AS SHC	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
0/2019. FHER IP.		CU28	LIGHT POLE BASE; REFER TO DETAIL CK-190. REFER TO LIGHTING, ELECTRICAL, AND STRUCTURAL PLANS BY OTHERS (TYP.). PROVIDE 2" CONDUIT FOR FUTURE ELECTRIC CHARGING	•	.15	
		CU39	STATION FROM BUILDING. STUB AND CAP 8" ABOVE FINISHED GRADE. CONDUIT RUNS BURIED A MINIMUM OF 24" BELOW GRADE AND HAVE A PULL STRING INSTALLED. CONDUIT RUNS MUST NOT EXCEED A TOTAL OF 180° DEGREES OF BEND WITHOUT A PULL BOX. STANDARD 90° BEND IS 6' BENDS WITH 3' RADIUS.		NC.1	
		U01 U02	EXISTING FIRE HYDRANT EXISTING WATER LINE; CONFIRM PRIOR TO CONSTRUCTION		_	
		U06	EXISTING SANITARY SEWER MANHOLE (TYP.)		NC	
		U07 U09	EXISTING SANITARY SEWER MAIN (TYP.) EXISTING UTILITY POLE (TYP.)		$\mathbf{\Sigma}$	
		U10 U13	EXISTING OVERHEAD UTILITY LINE (TYP.) EXISTING FORCE MAIN; CONFIRM PRIOR TO CONSTRUCTION		שאַ	
		U18	EXISTING GAS MAIN TO REMAIN	65		
		U19 U20	EXISTING TELEPHONE LINES TO REMAIN EXISTING UNDERGROUND POWER LINE TO REMAIN		Z Z	
		U31 U38	FIRE HYDRANT ASSEMBLY (TYP.) 6" GATE VALVE (TYP.)		WILMINGT	
		U39 U54	8" GATE VALVE (TYP.) 5' (INSIDE DIAMETER) MANHOLE			
.40		U54 U58	CONNECT TO EXISTING SANITARY SEWER MANHOLE. CORE DRILL AND INSTALL FLEXIBLE RUBBER BOOT. (CONTRACTOR TO FIELD VERIFY LOCATION AND ELEVATION)			PLAN
.40 .34		U72	COORDINATE WITH WATER DEPARTMENT TO ENSURE THAT SERVICE IS NOT INTERRUPTED AT ANY TIME.			
		U73 U74	30' WIDE CFPUA SANITARY SEWER EASEMENT. 20' WIDE CFPUA WATER EASEMENT.		ORT BL	
		U75	CIRCLE K / ILM RESPONSIBILITY PHASE LINE DELINEATES THE SCOPE OF WORK BREAKDOWN FOR THE PRIMARY WORK ON			E
2		U76	EACH PAGE (I.E. UTILITY WORK ON THE UTILITY PLAN).		N − N − N − N − N − N − N − N − N − N −	
$\overline{)}$		U77	ILM FUNDED CONSTRUCTION WORK		Õ '	
		U79 U80	PROPOSED 2" SADDLE CONNECTION PROPOSED 8" x 8" x 6" TEE		RPOR- TON - NEW H	
	+	U81 U82	PROPOSED 8" x 12" TS&V PROPOSED CORPORATION STOP			
			6" FIRE HYDRANT RPZ BACKFLOW PREVENTER (PER LOCAL			i
		U83	REQUIREMENTS). PROVIDE POWER TO HOT BOX. REFER TO DETAIL CK-240.			
/		U84	PROPOSED INSIDE DROP. REFER TO DETAIL.		Ζ	
					I	
					$\mathbf{X}$	
					Щ	
				Σ		
				· · · · · · · · · · · · · · · · · · ·		
					RO	


 $\bigcirc$ 

JOB NO.

SHEET NO.

C5.1


37630.054



ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

SHEET NO.

C5.2





└─ PROPOSED 8" X 12" TS&V

2.63

<u>21</u>. 73

<u>21</u> 60

10+50

21.

11+00

21.

42

11+50

<u>18.</u> 23.11

12+00

<u>.81</u>

*19.* 23.23

*20.* 23.31

12+50

17

<u>21.</u> 96


37

13+00

*21.* 1.61


13+50

14+00



PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

C5.3



#### PRIOR TO CONSTRUCTION LOCATE ALL UNDERGROUND UTILITIES WITHIN AND ADJACENT TO THE WORK AREA. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. PROTECT ALL UTILITIES. REPAIR ALL DAMAGE TO UTILITIES, STRUCTURES, SITE APPURTENANCES, ETC. WHICH

PRIOR TO THE COMMENCEMENT OF ANY ACTIVITIES REQUIRING A BUILDING OR ZONING PERMIT AN ON-SITE PRE-CONSTRUCTION CONFERENCE SHALL TAKE PLACE WITH THE DEVELOPER AND

o ANY PLANT MATERIAL WHICH IS DISEASED, DISTRESSED, DEAD, OR REJECTED (PRIOR TO SUBSTANTIAL COMPLETION) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH

CONTRACTOR IS ENCOURAGED TO COMPLETE TEMPORARY OR PERMANENT SEEDING IN STAGES FOR SOIL STABILIZATION AS AREAS ARE COMPLETED AFTER GRADING. THIS PLAN DOES NOT

• CONTRACTOR SHALL TAKE 3 REPRESENTATIVE SOIL SAMPLES OF EACH PROPOSED PLANT BED AND SUBMIT COPIES OF THE RESULTS TO THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING

• STUMPS LABELED FOR REMOVAL SHALL BE EXCAVATED, NOT GROUND. REMOVE ALL DEBRIS FROM THE HOLE. FILL WITH TOP SOIL, COMPACT, AND RAKE SMOOTH PRIOR TO INSTALLING NEW

CONTRACTOR IS RESPONSIBLE FOR DELIVERY SCHEDULE AND PROTECTION BETWEEN DELIVERY AND PLANTING TO MAINTAIN HEALTHY PLANT CONDITIONS.

• INSTALL LANDSCAPE PLANTINGS AT ENTRANCES/EXITS AND PARKING AREAS ACCORDING TO PLANS SO MATERIAL WILL NOT INTERFERE WITH SIGHT DISTANCES.

• AREAS DAMAGED FROM PLANT RELOCATION OR OTHER ACTIVITIES OF LANDSCAPE CONTRACTOR TO BE RESEEDED AND ESTABLISHED AT NO ADDITIONAL COST TO THE OWNER. CONTRACTOR IS RESPONSIBLE FOR WATERING ALL PLANT MATERIAL DURING INSTALLATION AND UNTIL FINAL INSPECTION AND ACCEPTANCE BY OWNER. CONTRACTOR SHALL NOTIFY OWNER OF USE HERBICIDES, PESTICIDES, AND FERTILIZER IN A MANNER CONSISTENT WITH THE FEDERAL INSECTICIDE, FUNGICIDE, AND RODENTICIDE ACT AND IN ACCORDANCE WITH LABEL RESTRICTIONS ALL LAWN AREAS TO BE SEEDED SHALL USE A LOCALLY GROWN COMMERCIAL MIX MEETING LATEST STATE OF NORTH CAROLINA AGRICULTURE STANDARDS FOR SEED AND PLANT

• REMOVE ALL LOOSE ROCKS, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE SMOOTH AND UNIFORM. DISPOSE OF WASTE MATERIAL OFF-SITE.

• APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPER PHOSPHATE UNIFORMLY AND MIX WITH SOIL. APPLY SOIL AMENDMENTS PER REQUIRED SOIL ANALYSIS RECOMMENDATIONS.

o INSPECT ALL SEEDED AREAS AND IF POSSIBLE, MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON. IF GRANDSTAND SHOULD BE OVER 60% DAMAGED,

• PLANTING BEDS TO BE COMPLETELY COVERED WITH A MINIMUM 4" DEPTH OF MATERIAL FROM A LOCAL SOURCE HARVESTED IN A SUSTAINABLE MANNER. REFER TO LANDSCAPE SCHEME FOR

• MULCH ALL PLANT BEDS AND TREE RINGS WITH FRESH, CLEAN MATERIAL PER SPECIFICATIONS. ALL MULCH EDGES SHALL BE NEATLY TUCKED. ALL STRING AND/OR BAILING WIRE SHALL BE REMOVED. DUST SHRUBS AND GROUND COVER AFTER MULCHING TO REMOVE LOOSE MATERIAL FROM PLANTS. DO NOT PLACE MULCH IN CONTACT WITH THE TREE TRUNK: KEEP A MINIMUM OF

• MULCH AND NO-MOW MIXES SHALL BE REPLENISHED AS NEEDED, ESPECIALLY AFTER HEAVY RAIN EVENTS. IF NO-MOW MIX GERMINATES AT A RATE OF LESS THAN 90%, THEN REMOVE OTHER

CONTRACTOR TO PROVIDE AND MAINTAIN TEMPORARY IRRIGATION FOR SOD WITHIN THE STORMWATER CONTROL MEASURE UNTIL SOD BECOMES ESTABLISHED.

 LANDSCAPE CONTRACTOR SHALL NOTIFY GENERAL CONTRACTOR UPON COMPLETION OF LANDSCAPE INSTALLATION. CONTRACTOR WILL VERIFY COMPLETENESS INCLUDING THE REPLACEMENT • PLANT MATERIAL QUANTITIES AND SIZES WILL BE INSPECTED FOR COMPLIANCE WITH APPROVED PLANS BY A SITE PLAN REVIEW AGENT PRIOR TO THE RELEASE OF THE CERTIFICATE OF

CONTRACTOR TO GUARANTEE ALL PLANT MATERIALS FOR ONE FULL YEAR AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH. WARRANTY PERIOD SHALL BEGIN UPON


#### PLANT SCHEDULE

		000000000	MIN.	
PROV'D	BOTANICAL NAME	COMMON NAME	INSTALLATION SIZE	COMMENTS
12	QUERCUS TEXANA	NUTTAL OAK	1.5-2" CALIPER, 8-10' MIN. HEIGHT	STREET TREES
6	ACER BUERGERIANUM	TRIDENT MAPLE	1.5-2" CALIPER, 6-8' MIN. HEIGHT	PARKING LOT

84	DARUMA DWARF LOROPETALUM	LOROPETALUM	24"MIN. HT.	STREET PROTECTIVE YARD
96	ILEX CRENATA	HOOGENDORN HOLLY	24" MIN. HT.	STREET PROTECTIVE YARD
12	LIGUSTRUM JAPONICUM 'TEXANUM'	WAXLEAF PRIVET	3' MIN. HT.	BUFFER YARD

CYNODON DACTYLON	BERMUDA GRASS	SOD	
CYNODON DACTYLON	BERMUDA GRASS	SEED	
	BARK MULCH		

SCALE 1"=40'




09/21/2020

JOB NO.

7630.054

SHEET NO.

C6.0



#### LANDSCAPE NOTES:

- PRE-CONSTRUCTION
- OCCURS AS A RESULT OF CONSTRUCTION.
- CONTRACTOR ENGAGED IN LANDSCAPE IMPLEMENTATION SHALL BE A LANDSCAPE CONTRACTOR REGISTERED IN THE STATE OF NORTH CAROLINA. • VERIFY ALL PLANT MATERIAL QUANTITIES ON PLANS PRIOR TO BIDDING. PLANT LIST TOTALS ARE FOR CONVENIENCE ONLY AND MUST BE VERIFIED.
- PLANT MATERIAL SUBSTITUTIONS CAN ONLY OCCUR WITH PRIOR WRITTEN APPROVAL BY LANDSCAPE ARCHITECT
- THE ADMINISTRATOR TO REVIEW PROCEDURES FOR THE PROTECTION AND MANAGEMENT OF ALL LANDSCAPE ELEMENTS TO REMAIN. ALL PLANT MATERIALS ARE SUBJECT TO LANDSCAPE ARCHITECT APPROVAL BEFORE, DURING, AND AFTER INSTALLATION.
- MATERIAL OF THE SAME SPECIES, QUANTITY, AND SIZE.
- ALL PLANT MATERIALS AND INSTALLATION SHALL COMPLY WITH RECOMMENDATIONS AND REQUIREMENTS OF ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK".
- ALL PLANT MATERIAL SHALL BE HEALTHY, VIGOROUS, AND FREE OF PESTS AND DISEASE. • ALL PLANT MATERIAL SHALL BE CONTAINER GROWN OR BALLED AND BURLAPPED AS INDICATED IN THE PLANT LIST. o ALL TREES SHALL HAVE A STRAIGHT TRUNK AND FULL HEAD.

CONSTRUCTION/INSTALLATION


- PRESENT ANY TEMPORARY STABILIZATION REQUIRED AS PART OF SWPPP PLAN.
- WORK.
- PLANT MATERIAL.
- CONTRACTOR IS RESPONSIBLE FOR DELIVERY SCHEDULE AND PROTECTION BETWEEN DELIVERY AND PLANTING TO MAINTAIN HEALTHY PLANT CONDITIONS. • ALL LANDSCAPED AND LAWN AREAS ARE TO RECEIVE A MINIMUM OF 4" OF TOPSOIL
- ALL LANDSCAPE ISLANDS SHALL BE GRADED FOR POSITIVE DRAINAGE WITH NO LOW SPOTS ALLOWING WATER TO BE TRAPPED.
- THE SIZE OF THE PLANTING AREA AND SIZE OF PLANT MATERIAL AT MATURITY SHALL ALLOW FOR A 2.5' BUMPER OVERHANG FROM THE BACK OF CURB.
- ALL TREES MUST BE GUYED OR STAKED AS DETAILED.
- CONDITIONS WHICH AFFECTS THE GUARANTEE. IT MAY BE NECESSARY TO TRUCK IN NON-CITY WATER TO MEET PLANT NEEDS.
- CERTIFICATION. SEEDING AND STRAW NOTES FOR LAWN AREAS:
- o RIP THE ENTIRE AREA TO DEPTH OF NOT LESS THAN 6".
- CHISEL COMPACTED AREAS AND SPREAD TOPSOIL TO SPECIFIED DEPTH.
- CONTINUE TILAGE UNTIL A WELL PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED.
- SEED ON A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.
- REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER, AND SEEDING RATES. o ANCHOR TACK WITH LIQUID ASPHALT AT 400 GAL/ACRE OR EMULSIFIED ASPHALT AT 300 GAL/ACRE.
- BIODEGRADABLE WEED MATTING (ALL-PRO WEED MAT OR APPROVED EQUAL) SHALL BE REQUIRED IN SHRUB BEDS ADJACENT TO BUILDING FACADE.
- MATERIAL SPECIFICATIONS.
- 4" AWAY FROM TREE TRUNK OR BASE OF PLANT.
- SPECIES AND RESEED.

#### **TEMPORARY IRRIGATION**

CONTRACTOR TO PROVIDE AND MAINTAIN TEMPORARY IRRIGATION FOR SOD WITHIN THE STORMWATER CONTROL MEASURE UNTIL SOD BECOMES ESTABLISHED.

INSPECTIONS/GUARANTEE

- OF ALL DEAD PLANT MATERIAL. CONTRACTOR IS RESPONSIBLE FOR SCHEDULING A FINAL INSPECTION BY LANDSCAPE ARCHITECT.
- OCCUPANCY.
- CERTIFICATE OF OCCUPANCY OR WHEN THE OWNER TAKES OVER MAINTENANCE, WHICHEVER COMES FIRST.



### PRELIMINARY - NOT RELEASED FOR CONSTRUCTION

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

#### PRIOR TO CONSTRUCTION LOCATE ALL UNDERGROUND UTILITIES WITHIN AND ADJACENT TO THE WORK AREA. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. PROTECT ALL UTILITIES. REPAIR ALL DAMAGE TO UTILITIES, STRUCTURES, SITE APPURTENANCES, ETC. WHICH

PRIOR TO THE COMMENCEMENT OF ANY ACTIVITIES REQUIRING A BUILDING OR ZONING PERMIT AN ON-SITE PRE-CONSTRUCTION CONFERENCE SHALL TAKE PLACE WITH THE DEVELOPER AND

o ANY PLANT MATERIAL WHICH IS DISEASED, DISTRESSED, DEAD, OR REJECTED (PRIOR TO SUBSTANTIAL COMPLETION) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH

CONTRACTOR IS ENCOURAGED TO COMPLETE TEMPORARY OR PERMANENT SEEDING IN STAGES FOR SOIL STABILIZATION AS AREAS ARE COMPLETED AFTER GRADING. THIS PLAN DOES NOT

• CONTRACTOR SHALL TAKE 3 REPRESENTATIVE SOIL SAMPLES OF EACH PROPOSED PLANT BED AND SUBMIT COPIES OF THE RESULTS TO THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING

• STUMPS LABELED FOR REMOVAL SHALL BE EXCAVATED, NOT GROUND. REMOVE ALL DEBRIS FROM THE HOLE. FILL WITH TOP SOIL, COMPACT, AND RAKE SMOOTH PRIOR TO INSTALLING NEW

• INSTALL LANDSCAPE PLANTINGS AT ENTRANCES/EXITS AND PARKING AREAS ACCORDING TO PLANS SO MATERIAL WILL NOT INTERFERE WITH SIGHT DISTANCES.

• AREAS DAMAGED FROM PLANT RELOCATION OR OTHER ACTIVITIES OF LANDSCAPE CONTRACTOR TO BE RESEEDED AND ESTABLISHED AT NO ADDITIONAL COST TO THE OWNER. CONTRACTOR IS RESPONSIBLE FOR WATERING ALL PLANT MATERIAL DURING INSTALLATION AND UNTIL FINAL INSPECTION AND ACCEPTANCE BY OWNER. CONTRACTOR SHALL NOTIFY OWNER OF USE HERBICIDES, PESTICIDES, AND FERTILIZER IN A MANNER CONSISTENT WITH THE FEDERAL INSECTICIDE, FUNGICIDE, AND RODENTICIDE ACT AND IN ACCORDANCE WITH LABEL RESTRICTIONS • ALL LAWN AREAS TO BE SEEDED SHALL USE A LOCALLY GROWN COMMERCIAL MIX MEETING LATEST STATE OF NORTH CAROLINA AGRICULTURE STANDARDS FOR SEED AND PLANT

• REMOVE ALL LOOSE ROCKS, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE SMOOTH AND UNIFORM. DISPOSE OF WASTE MATERIAL OFF-SITE.

• APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPER PHOSPHATE UNIFORMLY AND MIX WITH SOIL. APPLY SOIL AMENDMENTS PER REQUIRED SOIL ANALYSIS RECOMMENDATIONS.

• INSPECT ALL SEEDED AREAS AND IF POSSIBLE, MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON. IF GRANDSTAND SHOULD BE OVER 60% DAMAGED,

• PLANTING BEDS TO BE COMPLETELY COVERED WITH A MINIMUM 4" DEPTH OF MATERIAL FROM A LOCAL SOURCE HARVESTED IN A SUSTAINABLE MANNER. REFER TO LANDSCAPE SCHEME FOR

• MULCH ALL PLANT BEDS AND TREE RINGS WITH FRESH, CLEAN MATERIAL PER SPECIFICATIONS. ALL MULCH EDGES SHALL BE NEATLY TUCKED. ALL STRING AND/OR BAILING WIRE SHALL BE REMOVED. DUST SHRUBS AND GROUND COVER AFTER MULCHING TO REMOVE LOOSE MATERIAL FROM PLANTS. DO NOT PLACE MULCH IN CONTACT WITH THE TREE TRUNK: KEEP A MINIMUM OF

• MULCH AND NO-MOW MIXES SHALL BE REPLENISHED AS NEEDED, ESPECIALLY AFTER HEAVY RAIN EVENTS. IF NO-MOW MIX GERMINATES AT A RATE OF LESS THAN 90%, THEN REMOVE OTHER

 LANDSCAPE CONTRACTOR SHALL NOTIFY GENERAL CONTRACTOR UPON COMPLETION OF LANDSCAPE INSTALLATION. CONTRACTOR WILL VERIFY COMPLETENESS INCLUDING THE REPLACEMENT • PLANT MATERIAL QUANTITIES AND SIZES WILL BE INSPECTED FOR COMPLIANCE WITH APPROVED PLANS BY A SITE PLAN REVIEW AGENT PRIOR TO THE RELEASE OF THE CERTIFICATE OF


• CONTRACTOR TO GUARANTEE ALL PLANT MATERIALS FOR ONE FULL YEAR AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH. WARRANTY PERIOD SHALL BEGIN UPON

#### PLANT SCHEDULE

		000000000	MIN.		
PROV'D	BOTANICAL NAME	COMMON NAME	INSTALLATION SIZE	COMMENTS	
12	QUERCUS TEXANA	NUTTAL OAK	1.5-2" CALIPER, 8-10' MIN. HEIGHT	STREET TREES	
6	ACER BUERGERIANUM	TRIDENT MAPLE	1.5-2" CALIPER, 6-8' MIN. HEIGHT	PARKING LOT	

84	DARUMA DWARF LOROPETALUM	LOROPETALUM	24"MIN. HT.	STREET PROTECTIVE YARD
96	ILEX CRENATA	HOOGENDORN HOLLY	24" MIN. HT.	STREET PROTECTIVE YARD
12	LIGUSTRUM JAPONICUM 'TEXANUM'	WAXLEAF PRIVET	3' MIN. HT.	BUFFER YARD

CYNODON DACTYLON	BERMUDA GRASS	SOD	
CYNODON DACTYLON	BERMUDA GRASS	SEED	
	BARK MULCH		



09/21/2020


JOB NO.


7630.054

SHEET NO.

C6.1


SCALE 1"=40'





UNEXCAVATED OR TAMPED SOIL

WINDY SITES.



**EVERGREEN TREE - STAKING SPECIFIED** NOT TO SCALE

60

- PRUNE CODOMINATE LEADERS - RUBBER HOSE

SLIGHT AMOUNT OF MOVEMENT – 2"X2" HARDWOOD STAKE 2'-6" MIN BELOW SURFACE.

CONTAINER GROWN, REMOVE

- 1" COMPOST LAYER

PLASTIC PIPE; CAP FLUSH WITH MULCH

TRUNK FLARE - 6" SAUCER


TAMP SOIL AROUND ROOTBALL BASE FIRMLY WITH FOOT PRESSURE SO THAT ROOTBALL DOES NOT SHIFT


SEE PLANTING SCHEDULE (TYP.) MID COLUMN LOCATION (TYP.) -MULCH BED (TYP.)


**MID SIGN PLANTING DETAIL** NOT TO SCALE

PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS










se plans and associated documents are the exclusive property of TIMMONS GROUP and may not be reproduced in whole of in part a ed to construction, bidding, and/or construction staking without the express written consent of TIMMONS GROUP.



nmons.com\tgfs\300\332\37630-054-nti_airport_wilmi_nc\DWG\Sheet\CD\37630.054C-DETAILS.dwg | Plotted on 9/21/2020 10:51 AM | by Jacob Doole








*C7.6* 

PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



PRELIMINARY - NOT RELEASED FOR CONSTRUCTION


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL NEW HANOVER COUNTY, CAPE FEAR PUBLIC UTILITY AUTHORITY, NCDEQ, AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

JOB NO.

7630.054

SHEET NO.

C7.7



LABEL	ARRANGEMENT	LUMENS	LLF	BUG RATING	WATTS/LUMINAIRE	TOTAL WATTS	MANUFACTURER	CATALOG LOGIC
A3	SINGLE	10946	1.000	B1-U3-G2	80	240	HCT LIGHTING	F180-L-XXX-LED80W-5000K-III-9011BLACK + A361-1A-RAL9011
A4	SINGLE	10013	1.000	B2-U0-G5	79.6	477.6	HCT LIGHTING	F180-L-XXX-LED80W-5000K-IV-9011BLACK + A361-1A-RAL9011
A4-2	BACK-BACK	10013	1.000	B2-U0-G5	79.6	318.4	HCT LIGHTING	F180-L-XXX-LED80W-5000K-IV-9011BLACK + A361-2A-RAL9011
CAN	SINGLE	12516	1.020	B3-U0-G1	91.19	2918.08	Cree Lighting	CPY250-B-DM-F-13L-UL-XX-57K
L	SINGLE	1800	1.020	B1-U0-G0	20.5	225.5	Cree Lighting	LR6X-18L-40K-120V
SEC	SINGLE	10279	1.020	B3-U0-G3	134	268	CREE, INC.	SEC-EDG-3M-WM-06-E-UL-XX-700-40K

# red leonard asso

1340 Kemper Meadow Dr. | Cincinnati, OH 45240 | 513-574-9500 www.redleonard.com


	CATION SUMM	
LUM NO.	LABEL	MTG. HT.
1	A3	17
2	A3	17
3	A3	17
4	A4	17
5	A4	17
6	A4	17
7	A4	17
8	A4	17
9	A4	17
10	A4-2	17
11	A4-2	17
12	CAN	16
12	CAN	16
14	CAN	16
15		16
16	CAN	16
17	CAN	16
18	CAN	16
19	CAN	16
20	CAN	16
21	CAN	16
22	CAN	16
23	CAN	16
24	CAN	16
25	CAN	16
26	CAN	16
27	CAN	16
28	CAN	16
29	CAN	16
30	CAN	16
31	CAN	16
32	CAN	16
33	CAN	16
34	CAN	16
35	CAN	16
36	CAN	16
37	CAN	16
38	CAN	16
39	CAN	16
40	CAN	16
41	CAN	16
42	CAN	16
43	CAN	16
44	L	12
45	L	12
46	L	12
47	L	12
48	L	12
49	L	12
50	L	12
51	L	12
	L	12
52		
52 53	L	12
53		12 12
	L L SEC	12 12 10.5

- ALL AREA LIGHTS MOUNTED AT 17 FT. ON NEW BLACK ANODIZED ALUMINUM FLUTED POLES AT GRADE


GRADE USING INITIAL LUMEN VALUES							
	AVG	MAX	MIN	AVG/MIN	MAX/MIN		
	4.04	15.4	0.9	4.49	17.11		
	0.65	12.1	0.0	N.A.	N.A.		
	45.96	57	29	1.58	1.97		

PROJECT NAME:
CIRCLE K
WILMINGTON, NC
DRAWING NUMBER:
RL-6942-S1-R1





SCALE: LAYOUT BY: 1" = 30' FNE DWG SIZE: DATE: D 9/2/2020





ical D	lata*							
		System	Total C	urrent (A)				
le/ ator	System Watts 120-277V	Watts 347-480V; 347/480V	120V	208V	240V	277V	347V	480V
	60	68	0.51	0.29	0.25	0.22	0.20	0.14
	91	102	0.79	0.45	0.39	0.34	0.30	0.21
	96	96	0.82	0.47	0.40	0.35	0.28	0.20
	31	33	0.26	0.15	0.13	0.11	0.10	0.07
	145	145	1.22	0.70	0.61	0.53	0.42	0.30
	85	85	0.72	0.41	0.36	0.31	0.24	0.18

						22 C	
nt	Lumen Package/ Input Power Designator	Initial LMF	25K hr Reported ² LMF	50K hr Reported ² LMF	75K hr Estimated ³ LMF	100K hr Estimated ³ LMF	
	A/B/C/E/F	1.03	1.00	0.96	0.93	0.90	
	13L	1.04	1.01	1.00	0.98	0.97	
	A/B/C/E/F	1.02	0.99	0.95	0.92	0.89	
	13L	1.03	1.00	0.99	0.97	0.96	
	A/B/C/E/F	1.02	0.99	0.95	0.92	0.89	
	13L	1.02	0.99	0.98	0.96	0.95	
	A/B/C/E/F	1.01	0.98	0.95	0.91	0.88	
	13L	1.01	0.98	0.97	0.95	0.94	
	A/B/C/E/F	1.00	0.97	0.94	0.90	0.87	
	13L	1.00	0.97	0.96	0.94	0.93	
	A/B/C/E/F	0.99	0.96	0.93	0.90	0.87	
	13L	0.99	0.96	0.95	0.93	0.92	
nd ir nce fi lance	I 3L         U.77         U.76         U.73         U.73         U.73           aintenance values at 25° C177° F1 ar calculated per IST N+2 based on ISC N+40 report data for the LED f1 n-stu luminaire stating. Luminaire ambient temperature factors (LATF) have been applied to all lumon of actions. Plase are for to the <u>Imperature Zon Belference Document</u> for condice average inglithme ambient acre with IEST N+21, Reported values represent interplated values based on time durations that are up to &x duration in the ISC. M-40 report of the LED.						

ating Temperature Range							
n age/	Direct	Direct Mount	Class 1, Division 2 Hazardous Location				
r nator	Mount to Plywood	to Sheet Metal/ Suspended	Direct Mount to Plywood	Direct Mount to Sheet Metal/Suspended			
	-40°C to +40°C	-40°C to +45°C					
	-40°C to +35°C	-40°C to +40°C					
	-40°C to +45°C	-40°C to +50°C	-40°C to +25°C				
	-40°C to +35°C	-40°C to +40°C					
	-40°C to +40°C	-40°C to +45°C					
ING: Fx	ceeding maxi	mum operating t	emperature may result in ther	mal foldback			

roduc	t Description					Rev. Date: V2 08/28/2
he LR6 outstand 000 lun reakthi Iriver an eutral o	X [™] downlight is ding performanc nens of exceptio rough performan nd thermal man color temperatu	an unparalleled co te and value to the r nal 90+ CRI light wh nce is achieved by c agement design. Th res, three lumen pa	etrofit dowr nile achievir ombining th e LR6X™ do ickages, an	nlight space. Deliving up to 92 lumens ne high efficacy with ownlight is availab d offers a variety o	ering up to per watt, this h an integrated le in warm or	
		ial new constructior	and retrof	it		
	mance Summa s Cree TrueWhite®					
	Delivered Lumens					
	Power: 8 - 32.5 wat					
		.15				
CRI: 90						
		K (000)K				
	700K, 3000K, 3500					
	ed Warranty ⁺ : 10 ye					
	etime: > 100,000 ho					(135mm)
	ing: Dimmable to 5					2.9" [76mm]
	g & Trims	T or warranty dillin				
eference	Housing & Trim doo	cuments for more details	i			5.5"
Housing	gs					7.5">
	26) Base Housings I Housings, 120V	GU24 Base Housings Recessed Housings, 120	v	Wall Mount Housings, 120V	SC6-BL-277V - Textured black	
RC6 - New cor	nstruction	H6-GU24 - Architectural new cons		SC6-WM-GU24 - Textured white finish	finish	
RR6 RC6-GU24 - Retrofit - New construction			SC6-WM-BL-GU24 - Textured black finish	Housings SC6-CM-277V		
Recessed "Pan" Conversion Kit, 120V Retrofit			277V Connector Base	<ul> <li>Textured white finish</li> </ul>		
C6 Surface Mount Housings. Recessed "Pan" Conversion K C6-GU24		sion Kit, 120V	Housings 277V Recessed	- Textured black		
120V - Less socket adapter			Housings H6-277V - Architectural new	finish 277V Wall Mount Housings		
SC6-BL	d white finish	Surface Mount Housings <u>SC6-GU24</u> - Textured white finish	, 120V	construction RC6-277V	SC6-WM-277V - Textured white	
Cord Mou	d black finish unt Housings, 120V	- Textured black finish		- New construction RR6-277V	finish	
- Textures	d white finish	Cord Mount Housings, 13 SC6-CM-GU24	20V	- Retrofit 277V Recessed	Universal Recessed Housings, 120-277V	
and 7' (2	s 5" (127mm) canopy 2.1m) white cord	- Textured white finish     - Includes 5" (127mm) ca	nopy and 7	"Pan" Conversion Kit C6-277V-LSA	RC6-UNI - New	
- Texture	<u>BL</u> d black finish s 5° (127mm) canopy	[2.1m] white cord SC6-CM-BL-GU24	inopy and 7	- Less socket adapter 277V Surface Mount	Construction	
and 7' (2	2.1m) black cord	<ul> <li>Textured black finish</li> <li>Includes 5" (127mm) ca</li> </ul>	nopy and 7'	Housings SC6-277V	- Retrofit	
		(2.1m) black cord		- Textured white finish		
Trims						- 7
LXT6AB Diffuse Ar	nodized Reflector w/W	/hite Flange	8" Adapter GR8			Edison GU24 277V
LXT6BB	k Reflector w/Black Fl		<ul> <li>Optional go apertures from</li> </ul>	oof ring accommodates e om 6.25" (159mm) to 8.5'	xisting housings with ' (216mm) in diameter	
	ng Information					_
xample:	LR6X-7L-27K		-			
LR6X						
Series	Initial Delivered	Lumens	ССТ	Voltage	Base Type	
LR6X	7L 8W, 650 lumens – 81 LPW 10L 12.5W, 1,050 lumens – 84 LPW		27K 2700K	Blank 120-277 Volts	Blank Includes provisions fo	or mounting to E26 and GU24 sockets (120V), 120-277V rated LED orange
			30K 3000K			V), and traditional Cree Lighting 277V connectors (277V)
	18L 20.5W, 1,800 lumen	35K				
	24L 26W, 2,400 lumens		40K			
	30L		40501			
		c _ 92 I PW				
	32.5W, 3,000 lumen	s – 92 LPW		CREE		

Product	Description				
made from performan aluminum. J-Boxes. So sides and r through-wi	dge® wall mount lu rugged die cast alu ce aluminum heat s Includes a lightwei ecures to wall with ear. Allows mountii ring. Includes leaf/ <b>sis</b> General area an	uminum with integ sinks specifically o ght mounting box four 3/16" (5mm) ng for uplight or d debris guard.	gral, weath designed fo for install screws (by lownlight. I	ertight L or LED ap ation ove others).	ED drive plication r standa Conduit
Perform	ance Summary				
Patente	d NanoOptic® Produ	uct Technology			
Assemb	led in the U.S.A. of	U.S. and imported	d parts		
CRI: Mir	iimum 70 CRI				
CCT: 40	00K (+/- 300K), 5700	0K (+/- 500K) stan	Idard		
Limited	Warranty ⁺ : 10 year	rs on luminaire/10	) years on (	Colorfast	DeltaGu
CCESSOI					
					I-Held Rer
Bird Spikes		auty Plate			
XA-BRDSPH	: Wi Wi - C	auty Plate M-PLT12** - 12* [305; -PLT14** - 14* [356; overs holes left by in vall packs	mm) Square	- For pro	ENSREM successfu grammab one hand-h
XA-BRDSP/ Must specify ( Drdering	: we With a second s Information	M-PiIT3** - 12° (305) N-PIIT4** - 14° (356) covers holes left by in valt packs	mm) Square	- For pro	successfi grammab
XA-BRDSPY Must specify of Drdering Example: SE	: WM W W v olor	w-Pir1Y** - 12" (305) - PUF1Y** - 14" (356) covers holes left by in wall packs	mm) Square	- For pro of d	successfi grammab
XA-BRDSP/ Must specify (	: we With a second s Information	M-PiIT3** - 12° (305) N-PIIT4** - 14° (356) covers holes left by in valt packs	mm) Square cumbent	- For pro	successfi grammab
XA-BRDSP/ 'Must specify of <b>Ordering</b> Example: SE	: we With a second s Information	w-Pir1Y** - 12" (305) - PUF1Y** - 14" (356) covers holes left by in wall packs	mm) Square	- For pro of d	successfi grammab


ED Downlight – 6"	0											
Decifications The section of the se		Electrical	lata						_			
WHITE® TECHNOLOGY		Electricati	Jala		Total Current (A)							
ary way to generate high-quality white light, Cree TrueWhite® is a patented approach that delivers an exclusive combination peautiful light characteristics and lifelong color consistency, all aining high luminous efficacy – a true no compromise solution.		Lumen Package	Wa	stem tts )-277V	120V	rent (A	208V		24	ov	277V	
TION & MATERIALS aluminum housing protects the light source. Adjustable flip ide robust retention for fluck coiling fit		7L	8	-	0.08		0.05		0.0		0.04	
management system uses integral heat sink to conduct heat n LEDs for optimal performance. LED junction temperatures		10L 18L	20.		0.12		0.11		0.0		0.08	
ons		24L	26		0.23		0.13		0.1	1	0.10	
for insulated and non-insulated ceilings		30L	32.5	5	0.26		0.16		0.1	4	0.12	
e aluminum lower reflector redirects light while also 19 heat away from LEDs. It creates a comfortable visual 1 from the lens to the ceiling plane and easily accommodates p-in trims		* Electrical data at 25°C (77°F). Actual waitage may differ by +/-10% when operating between 120-277V +/- 10%										
STEM		LRX (LR6X	) Ser	ies Ambie	nt Adjuste	ed Lur	nen Ma	aintenan	:e1			
a uniform, comfortable appearance while eliminating n, hot spots and minimizing glare		Ambient		Lumen Package	Initial LMF	25K I Repo LMF		50K hr Reporte LMF	d²	75K hr Estimated ³ LMF	100K hr Estimate LMF	
ents work together to optimize distribution, balancing the of high illuminance levels on horizontal surfaces with an ideal		0°C (32°F)		All	1.03	1.00		0.97		0.95	0.93	
of light on walls and vertical surfaces. This increases the n of spaciousness		5°C (41°F)		All	1.03	1.00		0.97		0.95	0.93	
polycarbonate diffusing lens shields direct view of LEDs and		10°C (50°F)		All	1.02	0.99		0.96		0.94	0.92	
greater visual cut-off		15°C (59°F)		All	1.01	0.98		0.95		0.93	0.91	
L SYSTEM				7L-24L	1.01	1.01 0.98		0.95		0.93	0.91	
high-efficiency driver and power supply actor: > 0.9 (120V)		20°C (68°F)		30L	1.01	0.96		0.92		0.89	0.85	
monic Distortion: < 20% (120V)				7L-24L	1.00	0.97		0.95		0.92	0.90	
tage: 120V - 277V Universal, 50/60Hz		25°C [77°F]		30L	1.00	0.95		0.91		0.88	0.84	
immable to 5% with most incandescent dimmers									_			
immable to 5% with most trailing edge dimmers		30°C [86°F]		7L-18L	0.99	0.96		0.94		0.91	0.89	
e https://www.creelighting.com/products/indoor/retrofit-down-		00 0 (00 F)		24L-30L	0.99	0.93		0.88		0.83	0.79	
<u>-series</u> for recommended dimmers <b>g Temperature Range:</b> -25°C - +35°C (-13°F - +95°F);		35°C (95°F)		7L-18L	0.99	0.96		0.94		0.91	0.89	
ind 30L : -25°C - +30°C (-13°F - +86°F)										S LM-80 report d		


35°C (95°F)	7L-18L	0.99	0.96	0.94	0.91	0.89
¹ Lumen maintenance w package and in-situ lu maintenance factors. ² In accordance with IES up to 6x the tested dur ³ Estimated values are o	minaire testing TM-21, Repor ation in the IES	g. Luminaire : ted values re 5 LM-80 repo	ambient tempera present interpola rt for the LED.	ture factors (LAT ited values based	F) have been appli I on time durations	ied to all lumen s that are

hadvat Casaidiastiana									
roduct Specifications	Electrical D	ata*							
ONSTRUCTION & MATERIALS Slim, low profile design				Total Cu	rrent (A)				
Sum, low profile design Luminaire sides are rugged die cast aluminum with integral, weathertight LED driver compartment and high performance aluminum heat sinks specifically designed for LED applications	LED Count (x10)	Syst Watt 120-		120V	208V	240V	277V	347V	480V
Housing is rugged aluminum	350mA								
Furnished with low copper, light weight mounting box designed for installation over standard and mud ring single gang J-Boxes	02	25		0.21	0.13	0.11	0.10	0.08	0.07
Luminaire can also be direct mounted to a wall and surface wired	04	46		0.36	0.23	0.21	0.20	0.15	0.12
Secures to wall with four 3/16" (5mm) screws (by others)		-						-	
Conduit entry from top, bottom, sides, and rear Allows mounting for uplight or downlight	06	66		0.52	0.31	0.28	0.26	0.20	0.15
Designed and approved for easy through-wiring	08	90		0.75	0.44	0.38	0.34	0.26	0.20
Includes leaf/debris guard	10	110		0.92	0.53	-	0.41	0.37	0.24
Exclusive Colorfast DeltaGuard® finish features an E-Coat epoxy primer	10	110		0.92	0.53	0.47	0.41	0.32	0.24
with an ultradurable powder topcoat, providing excellent resistance to corrosion, ultraviolet degradation and abrasion. Black, bronze, silver and white are available	12	130		1.10	0.63	0.55	0.48	0.38	0.28
Weight: See Dimensions and Weight Chart on page 1	525mA	_					_		
LECTRICAL SYSTEM	02	37		0.30	0.19	0.17	0.16	0.12	0.10
Input Voltage: 120-277V or 347-480V, 50/60Hz, Class 1 drivers	04	70		0.58	0.34	0.31	0.28	0.21	0.16
Power Factor: > 0.9 at full load	06	101		0.84	0.49	0.43	0.38	0.30	0.22
Total Harmonic Distortion: < 20% at full load	08	133		1.13	0.66	0.58	0.51	0.39	0.28
Integral weathertight J-Box with leads (wire nuts) for easy power hook up	700mA	133	-	1.13	0.66	0.58	0.51	0.39	0.28
Integral 10kV surge suppression protection standard When code dictates fusing, a slow blow fuse or type C/D breaker should		1			1			1	
be used to address insing, a stow blow blow use of type CD breaker should be used to address inrush current Consult factory if in-luminaire fusing is required	02	50 93		0.41	0.25	0.22	0.20	0.15	0.12
Maximum 10V Source Current: 20 LED (350mA): 10mA;					0.40				
20LED (525 & 700 mA) and 40-120 LED: 0.15mA	06	134		1.14	0.65	0.57	0.50	0.39	0.29
EGULATORY & VOLUNTARY QUALIFICATIONS	* Electrical data at +/- 10%	t 25°C (7	/7°FJ. Actual	wattage ma	/ differ by +/·	- 10% when opera	ating betwee	120-277	V or 347-480
cULus Listed									
Suitable for wet locations Meets FCC Part 15, Subpart B, Class A limits for conducted and radiated emissions	Cree Edge®	Serie	s Ambien	t Adjuste	ed Lumer	Maintenand	:e ¹		
Enclosure rated IP66 per IEC 60529 when ordered without P or PML options	Ambient		nitial _MF	25K Repo	hr orted²	50K hr Reported ²	75K hr Estima		100K hr Estimate
ANSI C136.2 10kV surge protection, tested in accordance with IEEE/ANSI C62.41.2 $$	5°C (41°F)	_	.04	1.01		LMF	LMF 0.98		LMF
Luminaire and finish endurance tested to withstand 5,000 hours of elevated ambient salt fog conditions as defined in ASTM Standard B 117	10°C (50°F)		.04	1.00		0.98	0.97		0.95
DLC qualified with select SKUs. Refer to https://www.designlights.org/search/ for most current information	15°C (59°F)	1	.02	0.99		0.97	0.96		0.94
Meets Buy American requirements within ARRA CA RESIDENTS WARNING: Cancer and Reproductive Harm – www.poswarnings.ca.gov	20°C (68°F)	1	.01	0.98		0.96	0.95		0.93
	25°C (77°F)	1	.00	0.97		0.95	0.94		0.92
	<ol> <li>Lumen maintena package and in-si maintenance facto conditions.</li> <li>In accordance wi up to &amp; the tested</li> <li>Estimated values</li> </ol>	tu lumina ors. Plea th IES Th I duratio	aire testing. I ise refer to th M-21, Report in in the IES L	Luminaire a le <u>Temperal</u> ed values re _M-80 repor	nbient temp ure Zone Re present inter t for the LED	erature factors (L ference Documer rpolated values b	.ATF) have be at for outdoor ased on time	en applie average r durations	d to all lume nighttime am s that are

PERSONS USING THIS PROGRAM ARE ADVISED THAT THIS PROGRAM MAY CONTAIN ERRORS WHICH RED LEONARD ASSOCIATES, INC. OR ITS SOFTWARE PROVIDER HAVE NOT OBSERVED. IN ADDITION, THE USE OF THIS PROGRAM TO AID IN LAYOUT OF LIGHTING AND ESTIMATING MATERIAL QUANTITIES IS NOT INTENDED TO REMOVE THE RESPONSIBILITY OF THE USER TO VERIFY THE COMPLETENESS OF ANY BILL OF MATERIAL AND THAT THE LAYOUT OR USE OF LUMINAIRES IS IN FULL ACCORDANCE WITH ALL LOCAL, STATE, OR FEDERAL STATUTES, REGULATIONS OR OTHER REQUIREMENTS, OR THE REQUIREMENTS OF ANY INSURANCE GROUP, ORGANIZATION OR CARRIER REGARDING LUMINAIRES AND THEIR APPLICATION. STRICTLY PROHIBITED.

2 SEC SEC-EDG-3M-WM-06-E-UL-XX-700-40K





**CREE </u> LIGHTING** 

**CREE** <br/>
 LIGHTING

FOR INFORMATIONAL AND ILLUSTRATION PURPOSES ONLY. ALL PRODUCT, SERVICE AND CORPORATE NAMES ARE THE PROPERTY OF THEIR RESPECTIVE OWNERS. PRODUCT SPECIFICATIONS AND OUANTITIES MAY VARY. THESE DOCUMENTS ARE THE PROPERTY OF RED LEONARD ASSOCIATES, INC. ANY USE OF THESE DOCUMENTS WITHOUT THE WRITTEN CONSENT OF JAYME J. LEONARD OF RED LEONARD ASSOCIATES, INC. IS

# **CIRCLE K**

NTI AIRPORT BLVD WILMINGTON, NC

RL-6942-S1-R1